



STREET VIEW, NOT TO SCALE


DRAWING LIST:

DRAWING LIST		
Sheet Number	Sheet Name	Sheet Issue Date
A0.0	Cover Sheet	04/18/2023
A0.1	Life Safety Plan	04/18/2023
A0.2	Existing Site Plan	04/18/2023
A0.3	Proposed Site Plan	04/18/2023
A0.4	Erosion Control Plan	04/18/2023
A0.5	General Project Notes	04/18/2023
A1.1	Demolition Plan	04/18/2023
A1.2	Floor Plan	04/18/2023
A2.1	Existing Exterior Elevations	04/18/2023
A2.2	Existing Exterior Elevations	04/18/2023
A2.3	Exterior Elevations	04/18/2023
A2.4	Exterior Elevations	04/18/2023
A3.1	Exterior Wall Details	04/18/2023
A3.2	Door & Storefront Elevations	04/18/2023
A4.1	Accessibility Details	04/18/2023
A4.2	Stair & Ramp Details	04/18/2023
A4.3	Site Details	04/18/2023
E.1	Electrical Notes	11/30/2022
E.2	Power Floor Plan	11/30/2022
E.3	Lighting Floor Plan	11/30/2022
E.4	Roof Electrical Plan	11/30/2022
M-0.0	HVAC General Notes	11/30/2022
M-1.0	Mechanical Specifications	11/30/2022
M-2.0	HVAC Floor Plan Proposed	11/30/2022
M-3.0	HVAC Roof Plan	11/30/2022
M-4.0	Product Specifications	11/30/2022
M-5.0	Mechanical Details	11/30/2022
P-0.0	Plumbing General Notes	11/30/2022
P-1.0	Plumbing Site Plan	11/30/2022
P-2.0	Plumbing Floor Plan Proposed	11/30/2022
P-3.0	Plumbing Details	11/30/2022
P-4.0	Plumbing Specifications	11/30/2022

SYMBOLS LEGEND:

	NORTH ARROW
	First Floor Plan VIEW TITLE 1/8" = 1'-0"
	WALL SECTION INDICATOR
	ENLARGED PLAN INDICATOR
	LEVEL INDICATOR
	SINGLE ELEVATION INDICATOR
	EXTERIOR ELEVATION INDICATOR
	DOOR TAG
	WALL / PARTITION TYPE
	ALIGNING SURFACES
	CENTER LINE SYMBOL
	REVISION NUMBER
	PROPERTY LINE

LOCATION MAP:



SUMMARY OF WORK:

THIS PROJECT SCOPE INCLUDES THE INTERIOR RENOVATION FOR A RESTAURANT, ADDED ACCESSIBLE ENTRANCE, RESTROOMS, SITE CIRCULATION AND PARKING.

PROJECT INFORMATION:

1. ZONING DISTRICT CLASSIFICATION: C-2
2. PARCEL INFORMATION: 126L B 008.00 & 126L B 005.00
3. ACREAGE OF PROPERTY: 2.03 ACRES
4. EXISTING GROSS INTERIOR FLOOR AREA: 900 SF
5. PROPOSED GROSS INTERIOR FLOOR AREA: 2,642 SF
6. FAR: 0.029
7. PROPOSED OCCUPANCY CLASSIFICATION: A-2 (IBC 2018, SECTION 303.3)
8. CONSTRUCTION TYPE: TYPE V-B (IBC 2018, TABLE 601)
9. FIRE-RATING: 0 (IBC 2018, TABLE 601)
10. FIRE SEPARATION: 0 (IBC 2018, TABLE 602)

APPLICABLE CODES:

ADOPTED CODES - GATLINBURG CITY COMMISSION

THE 2018 EDITION OF THE INTERNATIONAL FIRE CODE
THE 2018 EDITION OF THE NATIONAL FIRE PROTECTION ASSOCIATION (NEPA 101) LIFE SAFETY CODE
THE 2018 EDITION OF THE INTERNATIONAL BUILDING CODE
THE 2018 EDITION OF THE INTERNATIONAL PLUMBING CODE
THE 2018 EDITION OF THE INTERNATIONAL FUEL GAS CODE
THE 2018 EDITION OF THE INTERNATIONAL ENERGY CONSERVATION CODE
THE 2018 EDITION OF THE INTERNATIONAL MECHANICAL CODE
THE 2018 EDITION OF THE INTERNATIONAL PROPERTY MAINTENANCE CODE
THE 2018 EDITION OF THE EXISTING BUILDING CODE
2009 ICC / ANSI A117.1 ACCESSIBLE AND USABLE BUILDINGS AND FACILITIES

GENERAL PROJECT NOTES:

1. COORDINATE WITH APPLICABLE DIMENSIONS AND DETAILS ON OTHER SHEETS.
2. COORDINATE WITH REQUIREMENTS OF OWNER SUPPLIED EQUIPMENT AS REQUIRED.
3. DIMENSIONS ARE TO FACE OF STUD OR OUTSIDE EDGE STRUCTURE.
4. THE CONTRACTOR SHALL LAYOUT ALL PARTITIONS AND VERIFY ACCEPTABILITY OF LAYOUT WITH OWNER PRIOR TO START OF THIS WORK.
5. DO NOT SCALE DRAWINGS, IF DIMENSIONS ARE IN QUESTION, THE CONTRACTOR SHALL OBTAIN WRITTEN CLARIFICATION FROM OWNER BEFORE CONTINUING WITH CONSTRUCTION

CLIENT INFORMATION:

GATLINBURG VITTALES, LLC
122 SPRUCE LN,
GATLINBURG, TN 37738
PHONE: 865-507-5897
EMAIL: LANCE@GCWORKSINC.COM

OWNER: BEVILLE REAGAN
REAGANS BROOKSIDE II LTD
PARTNERSHIP
PHONE: 865-567-0828
ADDRESS: 121 SILVERBELL LN
GATLINBURG, TN 37738
CONTACT: BEVILLE REAGAN

ARCHITECT:

TWO OAKS ARCHITECTURE, LLC
1809 N. HILLS BLVD
KNOXVILLE, TN 37917
PHONE: 615-972-6179
EMAIL: TAYLOR@TWOOAKSARCH.COM
CONTACT: TAYLOR HEIM EISENHOWER


2204 | Spruce Lane

PERMIT SET 122 Spruce Lane | Gatlinburg, TN 37738

04/18/2023



Approval for Demo Permit



DEMOLITION GENERAL NOTES:

- INTERIOR PARTITIONS SHALL BE REMOVED AND DISPOSED AS INDICATED ON THIS PLAN & LEGEND.
- CONTRACTOR SHALL PATCH AND REPAIR DRYWALL CEILING THAT IS EXISTING TO REMAIN.
- EXISTING DOORS, DOOR FRAMES & HARDWARE SHALL BE REMOVED. (UNLESS OTHERWISE NOTED)
- THE CONTRACTOR SHALL FURNISH ALL LABOR MATERIALS & EQUIPMENT TO DISCONNECT, DISMANTLE, REMOVE & SALVAGE IN THE DISPOSITION OF DEMOLITION IN EXISTING SPACE.
- CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PREVENT DAMAGE TO EXISTING STRUCTURE OR EQUIPMENT CAUSED BY THIS OPERATION AND SHALL NOT INTERFERE WITH EXISTING STRUCTURE SYSTEM.
- UPON COMPLETION OF DEMOLITION, THE ENTIRE AREA SHALL BE CLEANED OF ALL DEBRIS AND PREPARED FOR NEW CONSTRUCTION.
- EXISTING CONDITIONS NOT SHOWN ON THIS PLAN SHALL BE REVIEWED WITH OWNER PRIOR TO REMOVAL.
- THE CONTRACTOR SHALL PROVIDE ALL NECESSARY BARRICADES AND SAFETY BARRIERS AS REQUIRED BY WORK, CONTRACTOR TO PROVIDE DUST CONTROL MEASURES.

- WHERE EXISTING TILE FLOOR IS TO BE REMOVED, CONTRACTOR SHALL PREPARE SLAB TO BE LEVEL & SMOOTH, READY TO RECEIVE NEW FINISH.
- CONTRACTOR SHALL LOCATE, IDENTIFY, STUB-OFF AND DISCONNECT UTILITY SERVICES THAT ARE NOT INDICATED TO REMAIN. FILL SLAB WITH SAME FIRE RATED INTEGRITY. REMOVE ALL ELECTRICAL WIRE, J-BOXES, HOOKUPS, ETC., IN EXISTING PARTITIONS AND TIE-OFF AT SOURCE. REMOVE AND PLUG WATER LINES AT SOURCE. (ONLY IF SO DENOTED)
- ALL ITEMS OF SALVAGEABLE VALUE, AS DETERMINED BY THE OWNER, SHALL BE CAREFULLY REMOVED, CLEANED, STORED AND TURNED OVER TO THE BUILDING MANAGER, CONTRACTOR TO OBTAIN A RECEIPT. THESE ITEMS SHALL BE STORED FOR THE BUILDING IN AN AREA DESIGNATED BY THE BUILDING MANAGER.
- CONTRACTOR SHALL VISIT AND INSPECT SITE PRIOR TO BID.
- ALL CEILING FIRE ALARM DEVICES (SPEAKERS, SMOKE DETECTORS) SHALL REMAIN, CONNECTED TO EXISTING SYSTEMS. (REFER TO ENGINEERING DRAWINGS FOR ADDITIONAL INFORMATION)
- ALL EXISTING A/C DUCTWORK, DIFFUSERS (RETURN/SUPPLY) AIR DISTRIBUTION CONTRACTOR SHALL REMAIN. (REFER TO ENGINEERING DRAWINGS FOR ADDITIONAL INFORMATION)
- CONTRACTOR SHALL COORDINATE WORK WITH OTHER TRADES

- AND SHALL PROTECT THE BUILDING STRUCTURE AND ALL EXISTING MATERIAL AND EQUIPMENT NOT SCHEDULED FOR DEMOLITION.
- CONTRACTOR SHALL COORDINATE TO ENSURE UTILITY SYSTEMS REMAIN IN OPERATION AS NEEDED TO ACCOMMODATE DEMOLITION ACTIVITIES. COORDINATE INTERRUPTIONS TO UTILITIES WITH THE OWNER.
- CONTRACTOR SHALL PRACTICE ALL PRACTICAL CARE TO PROVIDE DUST AND NOISE CONTROL PROTECTION. COMPLY WITH GOVERNING REGULATIONS PERTAINING TO ENVIRONMENTAL PROTECTION.
- IF HAZARDOUS MATERIALS ARE ENCOUNTERED DURING DEMOLITION OPERATIONS, COMPLY WITH APPLICABLE REGULATIONS, LAWS AND ORDINANCES CONCERNING REMOVAL, HANDLING AND PROTECTION AGAINST EXPOSURE OR ENVIRONMENTAL POLLUTION.
- CONTRACTOR IS RESPONSIBLE FOR PROVIDING (FURNISHING AND INSTALLING) ALL ITEMS DESCRIBED IN THE DRAWINGS FOR A COMPLETE INSTALLATION REGARDLESS OF WHERE OR HOW IT IS SHOWN, UNLESS THEY ARE MARKED N.I.C. (NOT IN CONTRACT). CONTRACTOR SHALL COORDINATE AND FACILITATE INSTALLATION OF ALL ITEMS FOR WORK MARKED N.I.C. REFER TO DRAWINGS.

- CONTRACTOR SHALL OBTAIN ALL PERMITS WITH APPLICABLE BUILDING DEPARTMENTS AND SHALL OBSERVE AND FOLLOW ALL APPLICABLE ORDINANCES AND CODES.
- THE LATEST VERSION OF THE GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCTION BY THE AMERICAN INSTITUTE OF ARCHITECTS SHALL APPLY.
- CONTRACTOR SHALL REMOVE, CUT AND PATCH ALL EXISTING CONSTRUCTION AND FINISHES AS REQUIRED TO PREPARE THE PREMISES FOR NEW WORK AND ALTERED WORK.
- FOR ALL DEMOLITION WORK AND REMOVAL OF CONSTRUCTION DEBRIS, THE CONTRACTOR IS TO COORDINATE WITH THE BUILDING ENGINEER IN ORDER THAT IT WILL NOT INTERFERE WITH THE EXISTING TENANTS.
- ALL EXISTING SURFACES THAT ARE WITHIN THE SCOPE OF NEW WORK SHALL BE EXAMINED FOR CRACKS, WAVES, IMPERFECTIONS AND IRREGULARITIES. ALL SURFACES SHALL BE EITHER PATCHED OR PLASTERED AND MADE READY TO RECEIVE NEW FINISHES OR MADE TO MATCH OR ALIGN WITH ALL EXISTING MATERIALS AND FINISHES.
- REPAIR AND RESTORE, TO MATCH AND ALIGN WITH ALL EXISTING MATERIAL AND FINISH. ALL WORK BEYOND LIMITS OF NEW WORK THAT IS DAMAGED OR ALTERED DURING THE EXECUTION OF THE WORK IN THIS CONTRACT.

- THE CONTRACTOR IS RESPONSIBLE FOR ALL DAMAGE THAT OCCURS TO THE EXISTING BUILDING, OTHER FLOOR AREAS AND TENANT SPACE CAUSED BY THE NEW CONSTRUCTION.
- ALL SPRINKLER HEADS, DOWNLIGHTS, SPEAKERS, SMOKE DETECTORS AND ALL OTHER DEVICES, UNLESS OTHERWISE NOTED SHALL REMAIN AND OR BE REUSED/RELOCATED. (REFER TO ENGINEERING DRAWINGS FOR ADDITIONAL INFORMATION)
- ALL PENETRATION FIRESTOPS FOR METAL PIPE AND INSULATED PIPE SHALL BE IN ACCORDANCE WITH UNDERWRITERS LABORATORY TEST ASSEMBLY U.L. 1479.
- CONTRACTOR SHALL MAINTAIN THE INTEGRITY OF THE FIRE ENVELOPE DURING DEMOLITION AND CONSTRUCTION.
- CONTRACTOR SHALL NOTIFY DESIGNER OR CLIENT OF ANY EXISTING CONDITIONS NOT SHOWN ON THIS PLAN AND SHALL REVIEW THESE PRIOR TO PROCEEDING WITH WORK.
- ANY ELECTRICAL & PLUMBING LINES WHICH REQUIRE REMOVAL AND/OR ALTERATION CONTRACTOR SHALL CAP & FILL SLAB/PARTITION WITH SAME FIRE RATED INTEGRITY.
- ALL EXISTING FIRE EXTINGUISHERS SHALL REMAIN, UNLESS IMPACTED BY DEMOLITION. STORE EXTINGUISHERS IN IMPACTED AREA SHALL BE STORED FOR REUSE IN TENANT SPACE.

EXISTING/DEMO PLAN LEGEND:

- AREA NOT IN SCOPE - EXISTING TO REMAIN
- WALL TO REMAIN
- WALL TO BE DEMOLISHED
- DOOR TO REMAIN
- DOOR TO BE REMOVED

Spruce Lane


122 Spruce Lane | Gatlinburg, TN
37738

Client:
Lance Wayne, GC Works Inc.

twooaks architecture + planning

Revisions:

Issue:



Key Plan
© 2022 Two Oaks Architecture LLC

Demolition Plan

Date	11/30/2022
Scale	As indicated
Drawn By	GN
Checked By	THE
Project No.	2204
Sheet No.:	




A1.1


Spruce Lane

122 Spruce Lane | Gatlinburg, TN
37738

Client:
Lance Wayne, GC Works Inc.



1 South Elevation Existing
1/4" = 1'-0"




2 West Elevation Existing
1/4" = 1'-0"

EXISTING MATERIALS LEGEND:

- WD-01, WOOD SIDING
- ST-01, STONE
- WOOD POST
- CMU-01, CONCRETE MASONRY

Revisions:



Key Plan
© 2022 Two Oaks Architecture LLC

Existing Exterior Elevations

Date 11/30/2022
Scale 1/4" = 1'-0"
Drawn By GN
Checked By THE
Project No. 2204 Seal
Sheet No.:




A2.1


Spruce Lane

122 Spruce Lane | Gatlinburg, TN
37738

Client:
Lance Wayne, GC Works Inc.




1 North Elevation Existing
1/4" = 1'-0"



2 East Elevation Existing
1/4" = 1'-0"

Revisions:



Key Plan
© 2022 Two Oaks Architecture LLC

Existing Exterior Elevations

Date 11/30/2022
Scale 1/4" = 1'-0"
Drawn By GN
Checked By THE
Project No. 2204 Seal



A2.2


A0.1

Spruce Lane

122 Spruce Lane | Gatlinburg, TN
37738

Client:
Gatlinburg Vittales, LLC
122 Spruce Ln,
Gatlinburg, TN 37738

twooaks architecture + planning



EXISTING SITE PLAN GENERAL NOTES:

- THE TOPOGRAPHIC DATA WAS TAKEN FROM SEVIER COUNTY GIS & BOUNDARY DATA WAS TAKEN FROM OWNER PROVIDED SURVEY. VERIFY ALL DIMENSIONS AND CONDITIONS IN FIELD PRIOR TO COMMENCING THE WORK.
- PROPERTY CONCERNED IS REFLECTED IN THE CITY TAX MAP AS: MAP: 126L GROUP: B PARCEL 008.00
- ZONING FOR THE PROPERTY IS C-2
- TOTAL PARCEL AREA = 1.51 ACRES
TOTAL DISTURBED AREA = 0.96 ACRES
- OWNER: BEVILLE REAGAN
REAGAN'S BROOKSIDE II LTD PARTNERSHIP
121 SILVERBELL LN GATLINBURG, TN 37738
- PRIOR TO COMMENCING WORK, THE CONTRACTOR SHALL CONTACT THE UTILITY OWNERS TO NOTIFY THEM OF WORK IN

- THE AREA AND REQUEST THEM TO PROPERLY LOCATE THEIR RESPECTIVE UTILITY. NOTIFICATION SHALL BE GIVEN AT LEAST THREE BUSINESS DAYS PRIOR TO COMMENCEMENT OF OPERATIONS AROUND THE UTILITY.
- LOCATE EXISTING UTILITIES. CALL THE TENNESSEE ONE CALL SYSTEM AT 1-800-351-1111.
- CONTRACTOR SHALL PROVIDE ALL NECESSARY PROTECTIVE MEASURES TO SAFEGUARD THE EXISTING UTILITIES WHICH ARE TO REMAIN AND FURNISH ANY SPECIAL EQUIPMENT REQUIRED TO WORK OVER AND AROUND THE UTILITIES.
- CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND SITE CONDITIONS BEFORE STARTING WORK. ALL DIMENSIONS MARKED "V.I.F." SHALL BE VERIFIED IN THE FIELD BY THE CONTRACTOR. REPORT ALL DISCREPANCIES TO THE OWNER.
- PRIOR TO CONSTRUCTION, CONTRACTOR SHALL CONDUCT ONSITE MEETING TO IDENTIFY AND MARK LOCATIONS/METHODS

- OF TREE PROTECTION AND TO IDENTIFY SPECIFIC TREES TO BE REMOVED.
- UNLESS NOTED OTHERWISE, DIMENSIONS ARE TAKEN FROM THE FENCE LINE, PROPERTY LINE, FACE OF CURB, EDGE OF PAVEMENT OR OUTSIDE FACE OF BUILDING. IN THE EVENT DIMENSIONS ARE IN QUESTION OR IF ANY DISCREPANCIES ARE ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE OWNER FOR CLARIFICATION PRIOR TO PROCEEDING WITH THE WORK.
- THE MINERAL AGGREGATE BASE AND ASPHALTIC SURFACE COURSES SHALL MEET THE MATERIALS, EQUIPMENT CONSTRUCTION, AND TESTING REQUIREMENTS OF THE CITY OF GATLINBURG STANDARD SPECIFICATIONS.
- BUILDING SETBACKS ARE 15'-FT IN FRONT, 0'-FT ON SIDE AND 0'-FT IN REAR PER ARTICLE VIII OF THE CITY OF GATLINBURG MUNICIPAL ZONING ORDINANCE

- REFER TO ARCHITECTURAL PLANS FOR ACTUAL BUILDING DIMENSIONS AND DETAILS.
- FEMA PANEL:
THE SUBJECT PROPERTY LIES WITHIN A SPECIAL FLOOD HAZARD ZONE ACCORDING TO COMMUNITY PANEL NO. 47155C0334E, 05/18/2009, CITY OF GATLINBURG.

FLOODPLAIN BOUNDARY:


- ZONE AE, SPECIAL FLOOD HAZARD AREA
- ZONE X, 0.2% ANNUAL CHANCE FLOOD HAZARD

EXISTING SITE PLAN LEGEND

- PROPERTY LINE
- EDGE OF ROARING FORK RIVER
- SETBACK LINE
- EXISTING CONTOURS
- EXISTING BUILDING TO REMAIN
- EXISTING BUILDING TO BE DEMOLISHED
- EXISTING CONCRETE/ ASPHALT SIDEWALK, PARKING & DRIVEWAY
- EXISTING DIRT/ GRAVEL DRIVEWAY
- EXISTING FENCE TO BE DEMOLISHED
- EXISTING FENCE TO REMAIN
- EXISTING ROCKS / ROCK LEDGE
- EXISTING UTILITY POLE
- EXISTING FIRE HYDRANT
- EXISTING STORMWATER DRAIN
- EXISTING TREE TO REMAIN
- EXISTING TREE TO BE REMOVED

Revisions:

Issue:



Key Plan
© 2022 Two Oaks Architecture LLC

Existing Site Plan

Date 04/18/2023

Scale As indicated

Drawn By THE

Checked By JE

Project No. 2204 Seal

Sheet No.:




A0.2

Spruce Lane

122 Spruce Lane | Gatlinburg, TN
37738

Client:
Gatlinburg Vittales, LLC
122 Spruce Ln,
Gatlinburg, TN 37738



01 Proposed Site Plan
1" = 20'-0"

IMPERVIOUS AREA SUMMARY:

EXISTING IMPERVIOUS BUILDINGS SURFACE AREA: 5,650 SF
PROPOSED IMPERVIOUS BUILDINGS SURFACE AREA: 4,925 SF
EXISTING IMPERVIOUS DRIVES/SIDEWALKS SURFACE AREA: 8,840 SF
PROPOSED IMPERVIOUS DRIVES/SIDEWALKS SURFACE AREA: 19,360 SF
TOTAL PROPOSED IMPERVIOUS AREA: 0.56 AC. (24,285 SF)
PROPOSED LOT COVERAGE: 0.37

PARKING ANALYSIS:

REQUIRED PARKING SPACES: 1 PER 4 OCCUPANTS
90 OCCUPANTS / 4 = 22.5 OR 23 SPACES REQUIRED
PROPOSED PARKING SPACES: 27 SPACES
REQUIRED ADA PARKING SPACES: 1 PER 25 SPACES
27 SPACES / 25 = 1.1 OR 2 ADA SPACES REQUIRED
PROPOSED ADA PARKING SPACES: 2 SPACES

SITE PLAN GENERAL NOTES:


- CONTRACTORS AND SUBCONTRACTORS SHALL BE RESPONSIBLE FOR COORDINATION WITH OTHER TRADES. FAILURE TO FAMILIARIZE THEMSELVES WITH OTHER TRADES SHALL RESULT IN CORRECTING AND/OR PROVIDING THESE SERVICES AT NO ADDITIONAL COST TO THE OWNER.
- CONTRACTOR SHALL NOT SCALE THIS OR ANY OTHER DRAWING IN CONTRACT DOCUMENTS. DIMENSIONS SHALL ALWAYS BE USED FOR REFERENCE. CONTACT OWNER FOR ADDITIONAL DIMENSIONAL INFORMATION OR FOR CLARIFICATION CONCERNING ANY DISCREPANCIES.
- HANDLE AND DISPOSE OF DEBRIS, MATERIALS AND TRASH IN ACCORDANCE WITH ALL APPLICABLE CODES, STANDARDS AND REGULATIONS. PROVIDE OWNER WITH STAGING PLAN FOR DUMPSTER & OTHER EQUIPMENT.
- PROVIDE POSITIVE STORMWATER DRAINAGE AWAY FROM BUILDING AND DIRECT WATER AROUND THE BUILDING. ALL
- SWALES TO DIRECT STORMWATER AWAY FROM BUILDING
- PROVIDE TREE PROTECTION BARRIER AT DRIPLINE OF ALL TREES DESIGNATED TO BE PRESERVED THROUGHOUT CONSTRUCTION. ALL CONSTRUCTION STAGING PROHIBITED IN THESE AREAS.
- TREE LOCATIONS SHOWN ARE APPROXIMATE. VERIFY ALL DIMENSIONS AND CONDITIONS IN FIELD PRIOR TO COMMENCING THE WORK.
- COORDINATE DAYLIGHT LOCATIONS OF SITE DRAINAGE COMPONENTS WITH OWNER. PROVIDE RIVER ROCK AT DAYLIGHT LOCATION.
- AT COMPLETION OF PROJECT LEAVE DISTURBED LANDSCAPE STRAWED & SEEDDED FOR OWNER REPAIR.
- EXISTING LANDSCAPE FEATURES TO BE USED TO MEET LANDSCAPE PLAN REQUIREMENTS PER SECTION 407.3.4.1 OF THE CITY OF GATLINBURG MUNICIPAL ZONING ORDINANCE.

FLOODPLAIN BOUNDARY:

- ZONE AE, SPECIAL FLOOD HAZARD AREA
- ZONE X, 0.2% ANNUAL CHANCE FLOOD HAZARD

EXISTING SITE PLAN LEGEND

---	PROPERTY LINE	[Pattern]	CONCRETE/ ASPHALT SIDEWALK, PARKING & DRIVEWAY	●	EXISTING UTILITY POLE
- - -	EDGE OF ROARING FORK RIVER	[Pattern]	DIRT/ GRAVEL DRIVEWAY OR PATH	⬮	EXISTING FIRE HYDRANT
- - -	SETBACK LINE	▲	BUILDING ENTRANCE / EXIT	□	EXISTING STORMWATER DRAIN
---XXX' - X'	EXISTING CONTOURS	▲	EXISTING FENCE TO REMAIN	⊗	EXISTING TREE TO REMAIN
---	EXISTING BUILDING TO REMAIN	[Pattern]	EXISTING ROCKS / ROCK LEDGE		




Key Plan
© 2022 Two Oaks Architecture LLC

Proposed Site Plan

Date 04/18/2023
Scale As indicated
Drawn By GN
Checked By THE
Project No. 2204
Sheet No.:



A0.3



EROSION CONTROL GENERAL NOTES:

- EROSION CONTROL DEVICES SHALL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE TDEC'S EROSION AND SEDIMENT CONTROL HANDBOOK AND TDEC'S CONSTRUCTION ACTIVITY PERMIT REQUIREMENTS. THE CONTRACTOR SHALL PROVIDE ADDITIONAL EROSION CONTROL DEVICES AS NEEDED.
- APPLY TEMPORARY SEEDING WHENEVER GRADING OPERATIONS ARE TEMPORARILY HALTED FOR OVER 14 DAYS AND FINAL GRADING OF EXPOSED SURFACES IS TO BE COMPLETED WITHIN ONE YEAR. APPLY TEMPORARY SEEDING TO SOIL STOCKPILES.
- APPLY PERMANENT SEEDING WHENEVER GRADING OPERATIONS ARE COMPLETED AND ALL CONSTRUCTION OPERATIONS WILL NOT IMPACT THE DISTURBED AREA. APPLY PERMANENT SEEDING TO ALL NON-CONSTRUCTION AREAS, WHICH SHOW SIGNS OF EXCESSIVE EROSION.
- PERMANENT SEEDING SHALL BE DROUGHT TOLERANT, HYBRID KENTUCKY 31 (JAGUAR, LANCER, REBEL II, FALCON II, ETC.). SEED AT A RATE OF 6-8 LBS./1000 S.F. USE A SLOW RELEASE STARTER FERTILIZER WITH 1 LBS./1000 S.F. NITROGEN.

IF GRADING IS PERFORMED DURING THE WINTER MONTHS, SEED MIXTURE SHALL BE SUPPLEMENTED WITH A WINTER RYE OR OTHER APPROPRIATE MIXTURE TO ASSURE STABILIZATION DURING THE WINTER SEASON.

- MULCH WITH STRAW AT A RATE OF 100 LBS./1000 S.F. OVER THE SEEDED AREAS.
- THE CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF SITE CONSTRUCTION POLLUTION PREVENTION CONTROLS THROUGHOUT THE LIFE OF THE PROJECT.
- ADEQUATE DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES, BEST MANAGEMENT PRACTICES, AND/OR OTHER STORMWATER MANAGEMENT FACILITIES SHALL BE PROVIDED AND MAINTAINED AT ALL TIMES DURING CONSTRUCTION. DAMAGES TO ADJACENT PROPERTY AND/OR THE CONSTRUCTION SITE CAUSED BY THE CONTRACTOR'S FAILURE TO PROVIDE AND MAINTAIN ADEQUATE DRAINAGE, EROSION PREVENTION AND SEDIMENT CONTROL FOR THE CONSTRUCTION AREA SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

GRADING NOTES:

- THE GRADES SHOWN ON THESE DRAWINGS ARE APPROXIMATE BASED ON THE DATA PROVIDED BY THE OWNER. EXISTING GRADING IS TO REMAIN UNCHANGED AS POSSIBLE WITH NEW DESIGN.
- THE ACCURACY OF THE GRADES ARE DEPENDANT ON THE DATA PROVIDED BY THE OWNER. FIELD VERIFY PRIOR TO CONSTRUCTION.
- ALL TREES STUMPS AND OTHER OBSTRUCTIONS TO BE REMOVED SHALL BE REMOVED TO A DEPTH OF 2 FT BELOW THE SUBGRADE.
- STRIP TOPSOIL FULL DEPTH (6-IN. MIN.) AND TEMPORARILY STOCKPILE EXCAVATED MATERIALS. INSTALL SILT FENCE OR OTHER APPROPRIATE EROSION CONTROL STRUCTURES ON THE DOWN HILL SIDE OF THE STOCKPILE.
- AREAS THAT EXHIBIT WEAK SOIL OR OTHERWISE UNSUITABLE CONDITIONS SHALL BE UNDERCUT TO A FIRM LEVEL OF SOIL FOLLOWED BY BACKFILLING THE UNDERCUT AREAS USING AN ENGINEERED FILL. TDOT NO. 57, OR TDOT NO. 67 STONE.

- FILL MATERIAL SHALL BE SATISFACTORY MATERIAL FREE FROM ROOTS AND OTHER ORGANIC MATERIAL. FROZEN MATERIAL, AND TRASH. FILL MATERIAL SHALL ALSO BE FREE OF STONE OR OTHER MATERIAL LARGER THAN 6 IN. AND LARGER THAN 4 IN. IN THE TOP 6 IN. OF AN EMBANKMENT.
- FILL SOILS SHALL HAVE A PI LESS THAN 30 & A MAXIMUM DRY DENSITY OF 90 PCF OR GREATER.
- UNSATISFACTORY SOILS INCLUDE MATERIALS THAT ARE TOO WET OR TOO SOFT, EXPANSIVE SOILS AND SOILS CLASSIFIED PT. OH. AND OL. LEGALLY DISPOSE OF UNSATISFACTORY SOILS OFF-SITE UNLESS OTHERWISE APPROVED BY THE OWNER OR GEOTECHNICAL ENGINEER.
- FILL MATERIAL SHALL BE PLACED IN LOOSE, HORIZONTAL LIFTS NOT EXCEEDING 8 IN. THICKNESS. COMPACT EACH LAYER TO AT LEAST 98% MAXIMUM DRY DENSITY. COMPACT THE UPPER 24 IN. OF FILL BENEATH PAVEMENTS TO 100% MAXIMUM DRY DENSITY. MAINTAIN THE MOISTURE CONTENT TO WITHIN -1 TO +3 PERCENT OF THE OPTIMUM MOISTURE CONTENT.
- A 6 IN. (MIN.) LAYER OF TOPSOIL SHALL BE PLACED OVER THE

AREAS TO BE SEEDED AND TO THE FINISH GRADE ELEVATIONS AS SHOWN ON THE DRAWINGS.

- DO NOT ALLOW WATER TO ACCUMULATE IN EXCAVATIONS OR POND ON-SITE. PROVIDE NECESSARY MEASURES TO KEEP THE SITE FREE -DRAINING.
- PROTECT AND MAINTAIN SUBGRADES UNTIL PLACEMENT OF THE FINAL SURFACE IS ACHIEVED.
- VERIFY GRADES WHEREVER NECESSARY TO BRING THE PROPOSED LINES, ELEVATIONS, SLOPES, AND CROSS-SECTIONS OF THE GRADING WORK TO WITHIN THE FOLLOWING TOLERANCES ABOVE OR BELOW THAT AS SHOWN ON THE PLANS: UNPAVED AREAS 0.1', SIDEWALKS 0.10', PAVEMENTS 0.04
- DISTURBED AREAS SHALL BE STABILIZED IN AN EXPEDIENT MANNER TO MINIMIZE TIME OF EXPOSURE TO WEATHER.

01 Erosion Control Plan
1" = 20'-0"

Spruce Lane


122 Spruce Lane | Gatlinburg, TN
37738

Client:
Gatlinburg Vittales, LLC
122 Spruce Ln,
Gatlinburg, TN 37738

two|oaks architecture + planning

Revisions:

Issue:



Key Plan

© 2022 Two Oaks Architecture LLC

Erosion Control Plan

Date 04/18/2023

Scale As indicated

Drawn By THE

Checked By JE

Project No. 2204

Sheet No.:



A0.4

APPLIANCE NOTES:

COORDINATE ROUGH-IN AND INSTALLATION PER MFG. REQUIREMENTS.

COORDINATE APPLIANCES WITH THE CASEWORK PROVIDER.

ALL APPLIANCES ARE TO BE CONTRACTOR-PROVIDED AND CONTRACTOR INSTALLED.

COORDINATE POWER & DATA REQUIREMENTS FOR OWNER-PROVIDED EQUIPMENT WITH CASEWORK & ELECTRICAL DRAWINGS.

MECHANICAL & PLUMBING NOTES:

ALL WORK SHALL BE PERFORMED BY A LICENSED CONTRACTOR. CONTRACTOR IS TO PROVIDE ALL MATERIALS AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE SYSTEMS INDICATED ON THE DRAWINGS AS SPECIFIED AND AS REQUIRED BY ALL APPLICABLE CODES, ORDINANCES, AND AHJ.

INSTALL ALL EQUIPMENT AND APPLIANCES IN ACCORDANCE WITH MANUFACTURER INSTRUCTIONS AND RECOMMENDATIONS, AND ALL APPLICABLE CODES AND ORDINANCES.

THE CONTRACTOR IS RESPONSIBLE FOR THE COORDINATION OF THE FINAL INSTALLATION OF ALL EQUIPMENT AND SYSTEMS. COORDINATE ALL EQUIPMENT CONNECTIONS WITH THE MANUFACTURER'S DRAWINGS AND SPECIFICATIONS. COORDINATE AND PORIVED ALL DUCT AND PIPING TRANSITIONS REQUIRED FOR FINAL EQUIPMENT CONNECTIONS TO FURNISHED EQUIPMENT.

COORDINATE ALL MECHANICAL WORK WITH ANY ARCHITECTURAL, STRUCTURAL, CIVIL, ELECTRICAL SCOPE, ETC. SHOWN ON OTHER CONTRACT DOCUMENT DRAWINGS. MODIFICATIONS AND OFFSETS NECESSARY TO AVOID CONFLICTS AND INTERFERENCE WITH STRUCTURAL CONDITIONS AS WELL AS ALL OTHER DISCIPLINES AND TRADES SHALL BE PERFORMED AT NO COST TO THE OWNER.

BUILD ALL CHASES, RECESSES, SLEEVES, AND OTHER OPENINGS IN MASONRY, CONCRETE, OR OTHER MATERIALS AS THE CONSTRUCTION WORK PROGRESSES. IT SHALL BE THE SUBCONTRACTOR'S RESPONSIBILITY TO SEE SUCH CHASES, RECESSES, SLEEVES, AND OTHER OPENINGS ARE PROPERTY LOCATED AND INSTALLED. IF THIS IS NOT DONE, ANY CUTTING, PATCHING, OR BOTH, SHALL BE DONE AT THE SUBCONTRACTOR'S EXPENSE WHOSE WORK REQUIRED SUCH AN ACCOMMODATION.

WHERE TWO OR MORE ITEMS OF THE SAME TYPE OF EQUIPMENT ARE REQUIRED, THE PRODUCT OF ONE MANUFACTURER SHALL BE USED.

ALL CONTROL WIRING SHALL COMPLY WITH ALL APPLICABLE CODES, ORDINANCES, AND AHJ.

FIRE STOP ALL OPENINGS IN FIRE-RATED ASSEMBLIES DUE TO DUCTWORK, PIPING, CONDUIT, ETC. WITH A UL-LISTED FIRE STOP SYSTEM. INSTALL IN ACCORDANCE WITH ALL APPLICABLE CODES, ORDINANCES, AND AHJ.

UNLESS INDICATED OTHERWISE ON DRAWINGS, INTERNAL WATER PIPING IS TO BE ROUTED IN CEILING SPACES, ATTICS, CRAWL SPACES AND IN BETWEEN WALL STUDS, ETC, AND INSTALLED ON THE INSIDE OF THE BUILDING THERMAL ENVELOPE. INSTALLED IN ACCORDANCE WITH THE 2018 INTERNATIONAL PLUMBING CODE AND AHJ.

THE CONTRACTOR SHALL PROVIDE THE FOLLOWING ITEMS:
FURNISH ALL LABOR, MATERIALS, AND EQUIPMENT NECESSARY TO INSTALL MECHANICAL SYSTEMS AS SHOWN ON THE DRAWINGS AND SPECIFIED BELOW. THE MECHANICAL LAYOUT SHOWN IS FOR DIAGRAMMATIC PURPOSES ONLY. COMPLETE MECHANICAL SYSTEM LOAD CALCULATIONS, DESIGN, AND INSTALLATION TO BE PERFORMED BY A LICENSED MECHANICAL CONTRACTOR.

OBTAIN AND PURCHASE ALL PERMITS AND INSPECTIONS THAT ARE REQUIRED. RETAIN CERTIFICATES OF INSPECTION AND SUBMIT WHEN WORK IS COMPLETE.

GUARANTEE THAT ALL WORK IS IN ACCORDANCE WITH CONTRACT REQUIREMENTS AND FREE OF DEFECTS OR INFERRIAL MATERIALS, EQUIPMENT, AND WORKMANSHIP FOR A PERIOD OF ONE YEAR. GUARANTEE THAT ALL EQUIPMENT IS OF PROPER SIZE AND DESIGN SO INSTALLED AS TO PRODUCE THE CAPACITIES AND RESULTS REQUIRED. PROVIDE A FIVE-YEAR WARRANTY ON ALL AIR-CONDITIONING COMPRESSORS. WARRANTIES SHALL COMMENCE UPON SUBSTANTIAL COMPLETION AND OCCUPANCY BY THE OWNER. PROVIDE A ONE-YEAR PARTS AND LABOR WARRANTY ON ALL HVAC WORK AND EQUIPMENT.

PROVIDE THE OWNER WITH ONE PRINT OCPY AND AN ELECTRONIC COPY OF OPERATION AND MAINTENANCE MANUALS FOR ALL MECHANICAL EQUIPMENT.

MECHANICAL CONTRACTOR TO PROVIDE AIR SYSTEM BALANCE REPORT.

PROVIDE AIR SEALING BETWEEN ALL CONDITIONED AND UNCONDITIONED SPACES.

AT CONDITIONED CRAWL SPACE PROVIDE SPRAY APPLIED CONT. INSULATION W/ VAPOR BARRIER

ELECTRICAL NOTES:

ALL WORK MUST BE PERFORMED BY A LICENSED ELECTRICAL CONTRACTOR. THE CONTRACTOR SHALL REVIEW THE FINAL LOCATIONS OF ALL DEVICES WITH THE OWNER AND ARCHITECT PRIOR TO ROUGH-IN OR BEFORE THE WALL BOARD IS INSTALLED.

THE CONTRACTOR SHALL COORDINATE ALL POWER REQUIREMENTS WITH LIGHTING AND EQUIPMENT.

PROVIDE ELECTRICAL DISCONNECT AS REQUIRED BY CODE.

MOUNT OUTLETS AND OTHER DEVICES AT 18" A.F.F. UNLESS NOTED OTHERWISE.

MOUNT SWITCHES AT 48" A.F.F. UNLESS NOTED OTHERWISE.

PRIOR TO BEGINNING CONDUIT INSTALLATION FOR HVAC/PLUMBING EQUIPMENT ELECTRICAL CONTRACTOR SHALL CONFIRM WITH THE HVAC/PLUMBING CONTRACTOR THE VOLTAGES FOR ALL HVAC/PLUMBING EQUIPMENT REQUIRING ELECTRICAL SERVICE

WHERE APPLICABLE ALIGN LIGHT SWITCHES OVER RECEPTACLES.

ALL ELECTRICAL FIXTURES LOCATED IN AN EXTERIOR LOCATION OR IN WET/DAMP LOCATIONS SHOULD BE APPROPRIATE RATED FIXTURES OR HAVE WET LOCATION TRIM KITS.

FLOOD DAMAGE PREVENTION NOTES:

(AS OUTLINED IN THE FLOOD DAMAGE PREVENTION ORDINANCE, 14-305. FOR THE CITY OF GATLINBURG, TENNESSEE.)

A DEVELOPMENT PERMIT SHALL BE REQUIRED IN CONFORMITY WITH THIS ORDINANCE PRIOR TO THE COMMENCEMENT OF ANY DEVELOPMENT ACTIVITIES.

NO LAND, STRUCTURE OR USE SHALL HEREAFTER BE LOCATED, EXTENDED, CONVERTED OR STRUCTURALLY ALTERED WITHOUT FULL COMPLIANCE WITH THE TERMS OF THIS ORDINANCE AND OTHER APPLICABLE REGULATIONS.

NON-RESIDENTIAL STRUCTURES. WITHIN ALL FLOOD HAZARD AREAS WHERE FLOOD ELEVATION DATA IS AVAILABLE, NEW CONSTRUCTION AND SUBSTANTIAL IMPROVEMENT OF ANY COMMERCIAL, INDUSTRIAL, OR NON-RESIDENTIAL BUILDING, SHALL HAVE THE LOWEST FLOOR, INCLUDING BASEMENT, ELEVATED OR FLOODPROOFED TO NO LOWER THAN ONE FOOT (1') ABOVE THE LEVEL OF THE BASE FLOOD ELEVATION (100-YEAR FLOOD ELEVATION).

SHOULD SOLID FOUNDATION PERIMETER WALLS BE USED TO ELEVATE A STRUCTURE, OPENINGS SUFFICIENT TO FACILITATE EQUALIZATION OF FLOOD HYDROSTATIC FORCES ON BOTH SIDES OF EXTERIOR WALLS SHALL BE PROVIDED IN ACCORDANCE WITH THE STANDARDS OF THIS SECTION: "ENCLOSURES.

A REGISTERED ENGINEER OR LAND SURVEYOR SHALL CERTIFY THE FINISHED FLOOR ELEVATION.

ALL NEW CONSTRUCTION AND SUBSTANTIAL IMPROVEMENTS THAT INCLUDE FULLY ENCLOSED AREAS FORMED BY FOUNDATION AND OTHER EXTERIOR WALLS BELOW THE LOWEST FLOOR THAT ARE SUBJECT TO FLOODING, SHALL BE DESIGNED TO PRECLUDE FINISHED LIVING SPACE AND DESIGNED TO ALLOW FOR THE ENTRY AND EXIT OF FLOODWATERS TO AUTOMATICALLY EQUALIZE HYDROSTATIC FLOOD FORCES ON EXTERIOR WALLS.

DESIGNS FOR COMPLYING WITH THIS REQUIREMENT MUST EITHER BE CERTIFIED BY A TENNESSEE PROFESSIONAL ENGINEER OR ARCHITECT OR MEET OR EXCEED THE FOLLOWING MINIMUM CRITERIA:

(A) PROVIDE A MINIMUM OF TWO (2) OPENINGS HAVING A TOTAL NET AREA OF NOT LESS THAN ONE (1) SQUARE INCH FOR EVERY SQUARE FOOT OF ENCLOSED AREA SUBJECT TO FLOODING;

(B) THE BOTTOM OF ALL OPENINGS SHALL BE NO HIGHER THAN ONE FOOT (1') ABOVE THE FINISHED GRADE;

(C) OPENINGS MAY BE EQUIPPED WITH SCREENS, LOUVERS, VALVES OR OTHER COVERINGS OR DEVICES PROVIDED THEY PERMIT THE AUTOMATIC FLOW OF FLOODWATERS IN BOTH DIRECTIONS.

THE ENCLOSED AREA SHALL BE THE MINIMUM NECESSARY TO ALLOW FOR PARKING OF VEHICLES, STORAGE OR BUILDING ACCESS.

THE INTERIOR PORTION OF SUCH ENCLOSED AREA SHALL NOT BE FINISHED OR PARTITIONED INTO SEPARATE ROOMS IN SUCH A WAY AS TO IMPEDE THE MOVEMENT OF FLOODWATERS AND ALL SUCH PARTITIONS SHALL COMPLY WITH THE PROVISIONS OF 14-307(2)

FLOOD HAZARD REDUCTION NOTES:

(AS OUTLINED IN THE FLOOD DAMAGE PREVENTION ORDINANCE, 14-307. FOR THE CITY OF GATLINBURG, TENNESSEE.)

IN ALL FLOOD HAZARD AREAS, THE FOLLOWING PROVISIONS ARE REQUIRED:

(A) NEW CONSTRUCTION AND SUBSTANTIAL IMPROVEMENTS SHALL BE ANCHORED TO PREVENT FLOTATION, COLLAPSE AND LATERAL MOVEMENT OF THE STRUCTURE

(B) NOT APPLICABLE

(C) NEW CONSTRUCTION AND SUBSTANTIAL IMPROVEMENTS SHALL BE CONSTRUCTED WITH MATERIALS AND UTILITY EQUIPMENT RESISTANT TO FLOOD DAMAGE;

(D) NEW CONSTRUCTION AND SUBSTANTIAL IMPROVEMENTS SHALL BE CONSTRUCTED BY METHODS AND PRACTICES THAT MINIMIZE FLOOD DAMAGE;

(E) ALL ELECTRICAL, HEATING, VENTILATION, PLUMBING, AIR CONDITIONING EQUIPMENT, AND OTHER SERVICE FACILITIES SHALL BE DESIGNED AND/OR LOCATED SO AS TO PREVENT WATER FROM ENTERING OR ACCUMULATING WITHIN THE COMPONENTS DURING CONDITIONS OF FLOODING;

(F) NEW AND REPLACEMENT WATER SUPPLY SYSTEMS SHALL BE DESIGNED TO MINIMIZE OR ELIMINATE INFILTRATION OF FLOODWATERS INTO THE SYSTEM;

(G) NEW AND REPLACEMENT SANITARY SEWAGE SYSTEMS SHALL BE DESIGNED TO MINIMIZE OR ELIMINATE INFILTRATION OF FLOODWATERS INTO THE SYSTEMS AND DISCHARGES FROM THE SYSTEMS INTO FLOODWATERS;

(H) ON-SITE WASTE DISPOSAL SYSTEMS SHALL BE LOCATED AND CONSTRUCTED TO AVOID IMPAIRMENT TO THEM OR CONTAMINATION FROM THEM DURING FLOODING;

(I) ANY ALTERATION, REPAIR, RECONSTRUCTION OR IMPROVEMENTS TO A BUILDING THAT IS IN COMPLIANCE WITH THE PROVISIONS OF THIS ORDINANCE, SHALL MEET THE REQUIREMENTS OF "NEW CONSTRUCTION" AS CONTAINED IN THIS ORDINANCE;

(J) ANY ALTERATION, REPAIR, RECONSTRUCTION OR IMPROVEMENTS TO A BUILDING THAT IS NOT IN COMPLIANCE WITH THE PROVISION OF THIS ORDINANCE, SHALL BE UNDERTAKEN ONLY IF SAID NON-CONFORMITY IS NOT FURTHER EXTENDED OR REPLACED;

(K) ALL NEW CONSTRUCTION AND SUBSTANTIAL IMPROVEMENT PROPOSALS SHALL PROVIDE COPIES OF ALL NECESSARY FEDERAL AND STATE PERMITS, INCLUDING SECTION 404 OF THE FEDERAL WATER POLLUTION CONTROL ACT AMENDMENTS OF 1972, 33 USC 1334;


Spruce Lane

122 Spruce Lane | Gatlinburg, TN 37738

Client:
Gatlinburg Vittales, LLC
122 Spruce Ln,
Gatlinburg, TN 37738

two|oaks architecture + planning

Revisions:



Key Plan
© 2022 Two Oaks Architecture LLC

General Project Notes

Date	04/18/2023
Scale	
Drawn By	THE
Checked By	JE
Project No.	2204
Sheet No.:	




A0.5

Spruce Lane

122 Spruce Lane | Gatlinburg, TN
37738

Client:
Gatlinburg Vittales, LLC
122 Spruce Ln,
Gatlinburg, TN 37738



DEMOLITION GENERAL NOTES:

- INTERIOR PARTITIONS SHALL BE REMOVED AND DISPOSED AS INDICATED ON THIS PLAN & LEGEND.
- CONTRACTOR SHALL PATCH AND REPAIR DRYWALL CEILING THAT IS EXISTING TO REMAIN.
- EXISTING DOORS, DOOR FRAMES & HARDWARE SHALL BE REMOVED. (UNLESS OTHERWISE NOTED)
- THE CONTRACTOR SHALL FURNISH ALL LABOR MATERIALS & EQUIPMENT TO DISCONNECT, DISMANTLE, REMOVE & SALVAGE IN THE DISPOSITION OF DEMOLITION IN EXISTING SPACE.
- CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PREVENT DAMAGE TO EXISTING STRUCTURE OR EQUIPMENT CAUSED BY THIS OPERATION AND SHALL NOT INTERFERE WITH EXISTING STRUCTURE SYSTEM.
- UPON COMPLETION OF ALL DEBRIS AND PREPARED FOR NEW CONSTRUCTION.
- EXISTING CONDITIONS NOT SHOWN ON THIS PLAN SHALL BE REVIEWED WITH OWNER PRIOR TO REMOVAL
- THE CONTRACTOR SHALL PROVIDE ALL NECESSARY BARRICADES AND SAFETY BARRIERS AS REQUIRED BY WORK. CONTRACTOR TO PROVIDE DUST CONTROL MEASURES.

- WHERE EXISTING TILE FLOOR IS TO BE REMOVED, CONTRACTOR SHALL PREPARE SLAB TO BE LEVEL & SMOOTH, READY TO RECEIVE NEW FINISH.
- CONTRACTOR SHALL LOCATE, IDENTIFY, STUB-OFF AND DISCONNECT UTILITY SERVICES THAT ARE NOT INDICATED TO REMAIN. FILL SLAB WITH SAME FIRE RATED INTEGRITY. REMOVE ALL ELECTRICAL WIRE, J-BOXES, HOOKUPS, ETC., IN EXISTING PARTITIONS AND TIE-OFF AT SOURCE. REMOVE AND PLUG WATER LINES AT SOURCE. (ONLY IF SO DEVOTED)
- ALL ITEMS OF SALVAGEABLE VALUE, AS DETERMINED BY THE OWNER, SHALL BE CAREFULLY REMOVED, CLEANED, STORED AND TURNED OVER TO THE BUILDING MANAGER, CONTRACTOR TO OBTAIN A RECEIPT. THESE ITEMS SHALL BE STORED FOR THE BUILDING IN AN AREA DESIGNATED BY THE BUILDING MANAGER.
- CONTRACTOR SHALL VISIT AND INSPECT SITE PRIOR TO BID.
- ALL CEILING FIRE ALARM DEVICES (SPEAKERS, SMOKE DETECTORS) SHALL REMAIN, CONNECTED TO EXISTING SYSTEMS. (REFER TO ENGINEERING DRAWINGS FOR ADDITIONAL INFORMATION)
- ALL EXISTING A/C DUCTWORK, DIFFUSERS (RETURN/SUPPLY) AIR DISTRIBUTION CONTRACTOR SHALL REMAIN. (REFER TO ENGINEERING DRAWINGS FOR ADDITIONAL INFORMATION)
- CONTRACTOR SHALL COORDINATE WORK WITH OTHER TRADES


- AND SHALL PROTECT THE BUILDING STRUCTURE AND ALL EXISTING MATERIAL AND EQUIPMENT NOT SCHEDULED FOR DEMOLITION.
- CONTRACTOR SHALL COORDINATE TO ENSURE UTILITY SYSTEMS REMAIN IN OPERATION AS NEEDED TO ACCOMMODATE DEMOLITION ACTIVITIES. COORDINATE INTERRUPTIONS TO UTILITIES WITH THE OWNER.
- CONTRACTOR SHALL PRACTICE ALL PRACTICAL CARE TO PROVIDE DUST AND NOISE CONTROL PROTECTION. COMPLY WITH GOVERNING REGULATIONS PERTAINING TO ENVIRONMENTAL PROTECTION.
- IF HAZARDOUS MATERIALS ARE ENCOUNTERED DURING DEMOLITION OPERATIONS, COMPLY WITH APPLICABLE REGULATIONS, LAWS AND ORDINANCES CONCERNING REMOVAL, HANDLING AND PROTECTION AGAINST EXPOSURE OR ENVIRONMENTAL POLLUTION.
- CONTRACTOR IS RESPONSIBLE FOR PROVIDING (FURNISHING AND INSTALLING) ALL ITEMS DESCRIBED IN THE DRAWINGS FOR A COMPLETE INSTALLATION REGARDLESS OF WHERE OR HOW IT IS SHOWN, UNLESS THEY ARE MARKED N.I.C. (NOT IN CONTRACT). CONTRACTOR SHALL COORDINATE AND FACILITATE INSTALLATION OF ALL ITEMS FOR WORK MARKED N.I.C. REFER TO DRAWINGS.

- CONTRACTOR SHALL OBTAIN ALL PERMITS WITH APPLICABLE BUILDING DEPARTMENTS AND SHALL OBSERVE AND FOLLOW ALL APPLICABLE ORDINANCES AND CODES.
- THE LATEST VERSION OF THE GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCTION BY THE AMERICAN INSTITUTE OF ARCHITECTS SHALL APPLY.
- CONTRACTOR SHALL REMOVE, CUT AND PATCH ALL EXISTING CONSTRUCTION AND FINISHES AS REQUIRED TO PREPARE THE PREMISES FOR NEW WORK AND ALTERED WORK.
- FOR ALL DEMOLITION WORK AND REMOVAL OF CONSTRUCTION DEBRIS, THE CONTRACTOR IS TO COORDINATE WITH THE BUILDING ENGINEER IN ORDER THAT IT WILL NOT INTERFERE WITH THE EXISTING TENANTS.
- ALL EXISTING SURFACES THAT ARE WITHIN THE SCOPE OF NEW WORK SHALL BE EXAMINED FOR CRACKS, WAVES, IMPERFECTIONS AND IRREGULARITIES: ALL SURFACES SHALL BE EITHER PATCHED OR PLASTERED AND MADE READY TO RECEIVE NEW FINISHES OR MADE TO MATCH OR ALIGN WITH ALL EXISTING MATERIALS AND FINISHES.
- REPAIR AND RESTORE, TO MATCH AND ALIGN WITH ALL EXISTING MATERIAL AND FINISH, ALL WORK BEYOND LIMITS OF NEW WORK THAT IS DAMAGED OR ALTERED DURING THE EXECUTION OF THE WORK IN THIS CONTRACT.

- THE CONTRACTOR IS RESPONSIBLE FOR ALL DAMAGE THAT OCCURS TO THE EXISTING BUILDING, OTHER FLOOR AREAS AND TENANT SPACE CAUSED BY THE NEW CONSTRUCTION.
- ALL SPRINKLER HEADS, DOWNLIGHTS, SPEAKERS, SMOKE DETECTORS AND ALL OTHER DEVICES, UNLESS OTHERWISE NOTED SHALL REMAIN AND OR BE REUSED/RELOCATED. (REFER TO ENGINEERING DRAWINGS FOR ADDITIONAL INFORMATION)
- ALL PENETRATION FIRESTOPS FOR METAL PIPE AND INSULATED PIPE SHALL BE IN ACCORDANCE WITH UNDERWRITERS LABORATORY TEST ASSEMBLY UL 1479.
- CONTRACTOR SHALL MAINTAIN THE INTEGRITY OF THE FIRE ENVELOPE DURING DEMOLITION AND CONSTRUCTION.
- CONTRACTOR SHALL NOTIFY DESIGNER OR CLIENT OF ANY EXISTING CONDITIONS NOT SHOWN ON THIS PLAN AND SHALL REVIEW THESE PRIOR TO PROCEEDING WITH WORK.
- ANY ELECTRICAL & PLUMBING LINES WHICH REQUIRE REMOVAL AND/OR ALTERATION CONTRACTOR SHALL CAP & FILL SLAB/PARTITION WITH SAME FIRE RATED INTEGRITY.
- ALL EXISTING FIRE EXTINGUISHERS SHALL REMAIN, UNLESS IMPACTED BY DEMOLITION. STORE EXTINGUISHERS IN IMPACTED AREA SHALL BE STORED FOR REUSE IN TENANT SPACE.

EXISTING/DEMO PLAN LEGEND:

- AREA NOT IN SCOPE - EXISTING TO REMAIN
- WALL TO REMAIN
- WALL TO BE DEMOLISHED
- DOOR TO REMAIN
- DOOR TO BE REMOVED



Key Plan
© 2022 Two Oaks Architecture LLC

Demolition Plan

Date	04/18/2023
Scale	As indicated
Drawn By	GN
Checked By	THE
Project No.	2204
Sheet No.:	




A1.1

Spruce Lane

122 Spruce Lane | Gatlinburg, TN
37738

Client:
Gatlinburg Vittales, LLC
122 Spruce Ln,
Gatlinburg, TN 37738



01 Proposed Floor Plan
1/4" = 1'-0"

FLOOR PLAN GENERAL NOTES:


- DESIGN SCOPE INCLUDES MODIFICATION OF EXISTING SUSPECTED BEARING CONDITIONS. NEW STRUCTURAL MEMBERS AND CONNECTIONS SHALL COMPLY WITH THE DETAILING PROVISIONS OF THE INTERNATIONAL BUILDING CODE. LICENSED SUB-CONTRACTOR TO PROVIDE STRUCTURAL FRAMING DETAILS AS REQUIRED.
- PROVIDE ADEQUATE BRACING AND SHORING OF MODIFIED BEARING CONDITIONS PRIOR TO WORK. COORD. ANY ADDITIONAL FOUNDATION REQUIREMENTS FOR NEW BEARING CONDITIONS AS NECESSARY.
- FIELD VERIFY EXISTING CONDITIONS. COORDINATE NEW WORK WITH CONFIRMED CONDITIONS.
- COORDINATE MECHANICAL, ELECTRICAL, AND PLUMBING ITEMS AS RQD. FOR CONSTRUCTION. REFER TO LOCAL CODE COMPLIANCE AUTHORITIES.
- FIXTURES, FINISHES, APPLIANCES, AND EQUIPMENT ARE TO BE COORDINATED WITH THE OWNER.

WALL CONSTRUCTION GENERAL NOTES:


- REFER TO FLOOR PLAN FOR THE LOCATION OF PARTITION AND WALL TYPES. WALL TYPES TO BE AS FOLLOWS U.N.O:
 - A1 - INTERIOR WALLS - 2X4 STUDS AT 16" O.C. W/ GYP BD AT BOTH SIDES
 - A2 - INTERIOR WALLS - 2X4 STUDS AT 16" O.C. W/ GYP BD AT ONE SIDE
 - F1 - INTERIOR WALL FURRING - 1X2 FURRING STRIPS W/ GYP BD FINISH
 - F2 - EXTERIOR WALL FURRING - RIGID INSULATION, 1X2 FURRING W/ GYP BD FINISH AT INTERIOR
 - X1 - EXTERIOR WALLS - 2X6 STUDS AT 24" O.C. W/ GYP BD AT INTERIOR AND FIBER CEMENT SIDING AT EXTERIOR
 - E1 - EXISTING EXTERIOR INFILL WALL - INFILL EXISTING WALL WITH SIDING TO MATCH, VERIFY CONDITIONS IN FIELD.
 - E2 - EXISTING EXTERIOR INFILL WALL - INFILL EXISTING WALL WITH STONE TO MATCH, VERIFY CONDITIONS IN FIELD.

- CONTRACTOR SHALL INSTITUTE ALL MEASURES NECESSARY TO ACHIEVE WEATHER-TIGHTNESS OF EXTERIOR WALLS BY ALLOWING POSITIVE DRAINAGE OF WATER TO THE EXTERIOR TO OCCUR WHERE THROUGH-WALL FLASHING IS INDICATED OR RQD.
- AT CAVITY WALL CONSTRUCTION, ADHESIVE INSTALL THROUGH-WALL FLASHING ON CMU/CONCRETE OR SHEATHING OVER STUDS, UPWARD MIN. 6" AND PANUP THROUGH-WALL FLASHING AT ENDS MINIMUM 6". DO NOT MECHANICALLY FASTEN, PENETRATE, OR PUNCTURE THROUGH-WALL FLASHING. THROUGHWALL FLASHING TO DIRECT ALL MOISTURE TO EXTERIOR FACE OF WALL.
- PROVIDE CAULKED CONTROL JOINTS WHERE LOAD BEARING ABUTS NON-LOAD BEARING CONDITIONS OR WHERE WALLS OF DIFFERENT HEIGHTS ABUT.
- EXPOSED EARTH IN CRAWLSPACE TO BE COVERED W/ CLASS I VAPOR BARRIER RETARDER, SEAL, TAPE, AND OVERLAP JOINTS MIN. 6"


WALL TYPE A:



WALL TYPE F:




WALL TYPE X:



Revisions:

Issue:



Key Plan
© 2022 Two Oaks Architecture LLC

Floor Plan

Date 04/18/2023
Scale As indicated
Drawn By GN
Checked By THE
Project No. 2204
Sheet No.:




A1.2


Spruce Lane

122 Spruce Lane | Gatlinburg, TN
37738

Client:
Gatlinburg Vittales, LLC
122 Spruce Ln,
Gatlinburg, TN 37738



02 South Elevation Existing
1/4" = 1'-0"




01 West Elevation Existing
1/4" = 1'-0"

EXISTING MATERIALS LEGEND:

- WD-01, WOOD SIDING
- ST-01, STONE
- WOOD POST
- CMU-01, CONCRETE MASONRY

Revisions:

Issue:



Key Plan

© 2022 Two Oaks Architecture LLC

Existing Exterior Elevations

Date 04/18/2023

Scale 1/4" = 1'-0"

Drawn By GN

Checked By THE

Project No. 2204

Sheet No.:




A2.1


Spruce Lane

122 Spruce Lane | Gatlinburg, TN
37738

Client:
Gatlinburg Vittales, LLC
122 Spruce Ln,
Gatlinburg, TN 37738




02 North Elevation Existing
1/4" = 1'-0"



EXISTING MATERIALS LEGEND:

- WD-01, WOOD SIDING
- ST-01, STONE
- WOOD POST
- CMU-01, CONCRETE MASONRY

Revisions:



Key Plan
© 2022 Two Oaks Architecture LLC

Existing Exterior Elevations

01 East Elevation Existing
1/4" = 1'-0"


Date 04/18/2023
Scale 1/4" = 1'-0"
Drawn By GN
Checked By THE
Project No. 2204
Sheet No.:




A2.2

122 Spruce Lane | Gatlinburg, TN
37738

Client:
Gatlinburg Vittales, LLC
122 Spruce Ln,
Gatlinburg, TN 37738




02 South Elevation Proposed
1/4" = 1'-0"



01 West Elevation Proposed
1/4" = 1'-0"

PROPOSED MATERIALS LEGEND:



ENERGY CODE REQUIREMENTS

Alterations to existing buildings or structures are permitted without requiring the entire building or structure to comply with the energy requirements of the INTERNATIONAL ENERGY CONSERVATION CODE (2018 IECC). Alterations to the existing building have been designed to meet the requirements of the 2018 IECC Climate Zone 4.

SECTION C402.4.1


The vertical fenestration area, not including opaque doors and opaque spandrel panels, shall not be greater than 30 percent of the gross above-grade wall area.

TOTAL EXTERIOR WALL AREA PROPOSED:	2,724	SF
OPAQUE EXTERIOR WALL AREA:	1,952	SF
PROPOSED FENESTRATION AREA:	772	SF

2,724 * 0.30 = 817 SF ALLOWABLE FENESTRATION, COMPLIES

Revisions:

Issue:



Key Plan

© 2022 Two Oaks Architecture LLC

Exterior Elevations


Date	04/18/2023	
Scale	1/4" = 1'-0"	
Drawn By	GN	
Checked By	THE	
Project No.	2204	
Sheet No.:		Seal

A2.3


Spruce Lane

122 Spruce Lane | Gatlinburg, TN
37738

Client:
Gatlinburg Vittales, LLC
122 Spruce Ln,
Gatlinburg, TN 37738



02 North Elevation Proposed
1/4" = 1'-0"



01 East Elevation Proposed
1/4" = 1'-0"

PROPOSED MATERIALS LEGEND:

- WD-01, WOOD SIDING TO MATCH EXISTING
- ST-01, STONE TO MATCH EXISTING
- CMU-01, CONCRETE MASONRY TO MATCH EXISTING
- SF-0X, NEW STOREFRONT WALL

ENERGY CODE REQUIREMENTS

Alterations to existing buildings or structures are permitted without requiring the entire building or structure to comply with the energy requirements of the INTERNATIONAL ENERGY CONSERVATION CODE (2018 IECC). Alterations to the existing building have been designed to meet the requirements of the 2018 IECC Climate Zone 4.

SECTION C402.4.1


The vertical fenestration area, not including opaque doors and opaque spandrel panels, shall not be greater than 30 percent of the gross above-grade wall area.

TOTAL EXTERIOR WALL AREA PROPOSED: 2,724 SF
OPAQUE EXTERIOR WALL AREA: 1,952 SF
PROPOSED FENESTRATION AREA: 772 SF

2,724 * 0.30 = 817 SF ALLOWABLE FENESTRATION, COMPLIES

Revisions:

Issue:



Key Plan

© 2022 Two Oaks Architecture LLC

Exterior Elevations

Date 04/18/2023

Scale 1/4" = 1'-0"

Drawn By GN


Checked By THE

Project No. 2204


Sheet No.:




A2.4



05 STOREFRONT WALL HEAD DETAIL
3" = 1'-0"



03 STOREFRONT WALL BASE DETAIL
3" = 1'-0"



01 X1 - WALL SECTION 02
1/2" = 1'-0"

ENERGY CODE REQUIREMENTS

Alterations to existing buildings or structures are permitted without requiring the entire building or structure to comply with the energy requirements of the INTERNATIONAL ENERGY CONSERVATION CODE (2018 IECC). Alterations to the existing building have been designed to meet the requirements of the 2018 IECC Climate Zone 4.


TABLE C402.1.3

BUILDING COMPONENT	R-VALUE REQUIRED
ROOFS	
INSULATION ENTIRELY ABOVE ROOF DECK	R-30ci
ATTIC & OTHER	R-38
WALLS, ABOVE GRADE	
MASS	R-9.5ci
METAL FRAMED	R-13 + R-7.5ci
WOOD FRAMED & OTHER	R-13 + R-3.8ci or R-20
WALLS, BELOW GRADE	
BELOW GRADE WALLS	R-7.5ci
FLOORS	
MASS	R-10ci
JOISTS/FRAMING	R-30
SLAB ON GRADE FLOORS	
UNHEATED SLABS	R-10 for 24" below
OPAQUE DOORS	
NONSWINGING	R-4.75


TABLE C402.4

BUILDING COMPONENT	U-FACTOR REQUIRED
VERTICAL FENESTRATION	
FIXED FENESTRATION	0.38
OPERABLE FENESTRATION	0.45
ENTRANCE DOORS	0.77
ORIENTATION	SHGC REQUIRED
VERTICAL FENESTRATION	
PF < 0.2	SEW 0.36
N	0.48
0.2 ≤ PF < 0.5	SEW 0.43
N	0.53
PF ≥ 0.5	SEW 0.58
N	0.58

NOTE TO CONTRACTOR: Prior to the issuance of a Certificate of Occupancy, the Mechanical Subcontractor must provide proof of air system balancing capabilities, hydronic system balancing capabilities (if present) and an operating and maintenance manual to the Owner.



04 EXTERIOR WALL BASE DETAIL
3" = 1'-0"



02 X1 - WALL SECTION 01
1/2" = 1'-0"


Spruce Lane

122 Spruce Lane | Gatlinburg, TN
37738

Client:
Gatlinburg Vittales, LLC
122 Spruce Ln,
Gatlinburg, TN 37738

twooaks architecture + planning

Revisions:



Key Plan
© 2022 Two Oaks Architecture LLC

Exterior Wall Details

Date 04/18/2023

Scale As indicated

Drawn By THE


Checked By JE

Project No. 2204


Sheet No.:




A3.1




01 SF-01
1/4" = 1'-0"




02 SF-02
1/4" = 1'-0"




03 SF-03
1/4" = 1'-0"




04 SF-04
1/4" = 1'-0"




05 SF-05
1/4" = 1'-0"



06 SF-06
1/4" = 1'-0"



07 SF-07
1/4" = 1'-0"



08 SF-08
1/4" = 1'-0"

Door Schedule					
Mark	Comments	Width	Height	Construction Type	Frame Type
100	Existing Interior Door	2' - 6"	7' - 0"	VERIFY EXISTING CONDITIONS IN FIELD	V.I.F.
101	Existing Interior Door	2' - 10"	7' - 0"	VERIFY EXISTING CONDITIONS IN FIELD	V.I.F.
102	Interior Door, ADA Hardware Required	3' - 0"	7' - 0"	TYPE A, HOLLOW METAL - FLUSH SINGLE	TYPE 1
103	Interior Door, ADA Hardware Required	3' - 0"	7' - 0"	TYPE A, HOLLOW METAL - FLUSH SINGLE	TYPE 1
104	Interior Door	2' - 10"	7' - 0"	TYPE A, HOLLOW METAL - FLUSH SINGLE	TYPE 1
X-100	Existing Exterior Door	2' - 10"	7' - 8 1/2"	VERIFY EXISTING CONDITIONS IN FIELD	V.I.F.
X-101	Exterior Storefront Double Door, ADA Hardware Required	5' - 2"	7' - 8 1/2"	TYPE C2, ALUMINUM STOREFRONT	TYPE 3
X-102	Exterior Storefront Door, ADA Hardware Required	3' - 0"	7' - 8 1/2"	TYPE C1, ALUMINUM STOREFRONT	TYPE 3
X-103	Exterior Storefront Door, ADA Hardware Required	3' - 0"	7' - 8 1/2"	TYPE C1, ALUMINUM STOREFRONT	TYPE 3

DOOR LOCATION	DOOR LEGEND	DOOR FRAME TYPES	THRESHOLD
A. DOORS SHOWN ADJACENT TO A FLANKING WALL OR OTHER FIXED OBSTRUCTION, SHALL BE LOCATED AS SHOWN ABOVE. B. OTHER LOCATIONS SHALL BE ON CENTERLINE OF ROOM OR AS SPECIFICALLY DIMENSIONED.	A FLUSH SINGLE B CASED OPENING C1 ALUMINUM SINGLE C2 ALUMINUM DOUBLE	1 TYPICAL - HOLLOW METAL 2 CASE OPENING 3 TYPICAL - ALUMINUM	1/4" MAX 1/4" MAX 1/2" MAX 1/34" MAX FOR EXISTING ALTERED THRESHOLDS

CONTROL JOINT AT DOOR FRAMES	GYPSUM BD CONFIGURATION AT DOORS
EXTEND CJ TO BOTTOM OF STRUCTURE AT RATED WALLS 4" ABOVE CEILINGS AT NON- RATED WALLS ALIGN WITH EDGE OF DOOR FRAME CORNER ON HINGE SIDE EXTEND CJ TO BOTTOM OF STRUCTURE AT RATED WALLS 4" ABOVE CEILINGS AT NON-RATED WALLS ALIGN WITH EDGE OF DOOR FRAME CORNER EXTEND CJ TO BOTTOM OF STRUCTURE AT RATED WALLS 4" ABOVE CEILINGS AT NON- RATED WALLS ALIGN WITH EDGE OF CASED OPENING SINGLE DOORS DOUBLE DOORS CASED OPENING	BOTTOM OF STRUCTURE VARIES 4' X 8' GYP BD PANEL CONFIGURATION SINGLE DOORS DOUBLE DOORS

SAFETY GLASS LOCATIONS

NOTE:
NOT ALL CONDITIONS SHOWN BELOW ARE APPLICABLE TO THE SCOPE OF WORK.

GLASS SCHEDULE

GLASS PRODUCT SCHEDULE FOR WALLS AND DOORS						
NP - NOT PERMITTED	* - NOT ALLOWED AT SHOWER ENCLOSURES	ANNEALED	WIRED	TEMPERED	LAMINATED	FIRE-RATED
A - ACCEPTABLE						
NR - NOT RECOMMENDED						
FIRE-RATED	SAFETY NOT REQUIRED	NP	A	NP	NP	A
	SAFETY REQUIRED	NP	NP	NP	NP	A
NON-FIRE-RATED	SAFETY NOT REQUIRED	A	A	A	A	NR
	SAFETY REQUIRED	NP	NP	*	A	NR

SAFETY GLAZING (SG) IS REQUIRED FOR

CLOSE PROXIMITY TO DOORS

GLAZED OPENINGS IN DOORS

GLAZED OPENINGS IN PARTITIONS

SAFETY GLASS IS REQUIRED WHEN ALL OF THE FOLLOWING CONDITIONS ARE PRESENT:
* TOP OF GLAZING IS GREATER THAN / EQUAL 36" AFF
* AREA OF SINGLE PANE > 9 SF
* BOTTOM OF GLAZING IS LESS THAN / EQUAL 18" AFF
* WALKING SURFACE IS LOCATED WITHIN 36" OF ONE OR BOTH SIDES

EXCEPTION:
GLASS DOES NOT NEED TO BE SAFETY GLASS WHEN 1 1/2" SAFETY BAR IS INSTALLED WHERE WALKING SURFACE IS WITHIN 36" OF GLASS

SAFETY GLASS IS REQUIRED AT INTERIOR LITE WHEN BOTTOM OF GLAZING IS LESS THAN / EQUAL 18" AFF

EXCEPTION:
INTERIOR LITE DOES NOT NEED TO BE SAFETY GLASS WHEN 1 1/2" SAFETY BAR IS INSTALLED

SAFETY GLASS IS REQUIRED FOR EXTERIOR LITE EXCEPT WHEN THE BOTTOM OF THE GLAZING IS GREATER THAN / EQUAL 25 FT ABOVE GRADE

- DOOR CONSTRUCTION GENERAL NOTES:**
- SUBCONTRACTOR TO CONSULT WITH OWNER FOR KEYING AND HARDWARE REQUIREMENTS.
 - VERIFY FIELD MEASUREMENTS & R.O. DIMENSIONS PRIOR TO FABRICATION.
 - CONTRACTOR TO UNDERCUT DOORS AS REQUIRED TO ACHIEVE PROPER AIRFLOW AND MEET VENTILATION REQUIREMENTS.
 - HINGES TO MATCH DOOR HARDWARE. HINGE SIZE AND QUANTITY PER DOOR SIZE AND WEIGHT REQUIREMENTS. SEE HARDWARE MFG REQUIREMENTS.
 - ALL GLAZING TO BE CLEAR GLASS U.N.O. INSULATED UNITS TO BE GLAZED WITH LOW 'E' GLAZING AND ARGON-FILLED.
 - CONTRACTOR TO VERIFY R.O. SIZES FOR WINDOWS & DOORS AND COORDINATE WITH FRAMING.
 - DOORS TO MATCH FRAMES AT ALL LOCATIONS.
 - ALL GLAZING IN WINDOWS AND DOORS TO COMPLY WITH SAFETY GLAZING REQUIREMENTS AS REQUIRED BY BUILDING CODE AND MFG. RECOMMENDATIONS.
 - PROVIDE FULL-TEMPERED GLAZING UNITS AT ALL WINDOW LOCATIONS ADJACENT TO DOORS.
 - FLASH ALL OPENINGS TO ACCEPTABLE INDUSTRY AND APPLICABLE BUILDING CODE STANDARDS.
 - PROVIDE INSECT SCREENS AT ALL OPERABLE PANELS.

Spruce Lane


122 Spruce Lane | Gatlinburg, TN
37738

Client:
Gatlinburg Vittales, LLC
122 Spruce Ln,
Gatlinburg, TN 37738

twooaks architecture + planning

Revisions:

Issue:



Key Plan
© 2022 Two Oaks Architecture LLC

Door & Storefront Elevations

Date 04/18/2023
Scale As indicated
Drawn By GN
Checked By THE
Project No. 2204 Seal
Sheet No.:




A3.2




AT WALL BASE, PROVIDE RUBBER GUARD AS PER IBC


A4.1




06 HANDRAIL AND GUARDRAIL SECTION
1 1/2" = 1'-0"




05 HANDRAIL AND GUARDRAIL PLAN AT
TOP LANDING
1 1/2" = 1'-0"




04 RAILING AND GUARDRAIL ELEVATION
AT TOP LANDING
1" = 1'-0"



03 EGRESS STAIR SECTION
1/2" = 1'-0"



02 ADA RAMP SECTION
1/2" = 1'-0"



01 Egress Stair & ADA Ramp Plan
1/2" = 1'-0"


Spruce Lane

122 Spruce Lane | Gatlinburg, TN
37738

Client:
Gatlinburg Vittales, LLC
122 Spruce Ln,
Gatlinburg, TN 37738

twooaks architecture + planning

Revisions:



Key Plan
© 2022 Two Oaks Architecture LLC

Stair & Ramp Details

Date 04/18/2023

Scale As indicated

Drawn By THE


Checked By JE

Project No. 2204


Sheet No.:




A4.2




10 SIGNAGE BASE PLATE DETAIL
3" = 1'-0"




09 ACCESSIBLE PARKING SPACE SIGNAGE DETAIL
1/2" = 1'-0"




08 ADA VAN ACCESSIBLE PARKING SPACE LAYOUT
1/4" = 1'-0"




07 STANDARD PARKING SPACE LAYOUT
1/4" = 1'-0"




06 DUMPSTER ENCLOSURE WALL
1" = 1'-0"




05 SIDE ELEVATION
1/4" = 1'-0"




04 REAR ELEVATION
1/4" = 1'-0"



03 SIDE ELEVATION
1/4" = 1'-0"



02 FRONT ELEVATION
1/4" = 1'-0"



01 DUMPSTER ENCLOSURE
1/4" = 1'-0"


Spruce Lane

122 Spruce Lane | Gatlinburg, TN
37738

Client:
Gatlinburg Vittales, LLC
122 Spruce Ln,
Gatlinburg, TN 37738

twooaks architecture + planning

Revisions:



Key Plan
© 2022 Two Oaks Architecture LLC

Site Details

Date 04/18/2023

Scale As indicated

Drawn By THE

Checked By JE

Project No. 2204


Sheet No.:



A4.3

GENERAL ELECTRICAL NOTES

1. ALL WORK SHALL BE PERFORMED TO MEET THE REQUIREMENTS OF THE NFPA 70, NATIONAL ELECTRICAL CODE (2020 EDITION), NFPA 72 NATIONAL FIRE ALARM CODE (2016 EDITION), NFPA 101, LIFE SAFETY CODE (2018 EDITION), LOCAL AND STATE CODES AND ANY OTHER APPLICABLE CODES AND STANDARDS.
2. THE ELECTRICAL DESIGN IS BASED UPON THE AVAILABLE INFORMATION AT DESIGN TIME. CONTRACTOR TO REVIEW NAMEPLATE DATA AND MANUFACTURER SUPPLIED LITERATURE FOR ALL PIECES OF EQUIPMENT PRIOR TO ROUGH ELECTRICAL WIRING. THE CONTRACTOR SHALL CHECK NAMEPLATE DATA OF ALL EQUIPMENT FOR REQUIRED VOLTAGES, MINIMUM CIRCUIT AMPACITY AND OVERCURRENT PROTECTION. CONTRACTOR SHALL CONTACT ENGINEER PRIOR TO ANY FIELD ADJUSTMENT.
3. THE CONTRACTOR SHALL ENSURE THAT NEUTRAL WIRES AND EQUIPMENT GROUND WIRES ARE INSTALLED WHERE EVER APPLICABLE.
4. THESE DRAWINGS ARE DIAGRAMMATIC AND NOT INTENDED TO SHOW EVERY MINOR DETAIL. CIRCUITS ARE SYMBOLICALLY SHOWN TO DETERMINE LOAD DATA AND EQUIPMENT SIZES, AND THEY ARE ONLY A GUIDE FOR THE INSTALLATION OF ELECTRICAL SERVICE. DO NOT SCALE DRAWINGS FOR EXACT LOCATION OF EQUIPMENT. CONTRACTOR SHALL PHYSICALLY PROVIDE CIRCUITS AND ROUTING OF CONDUITS TO SUIT JOB CONDITIONS. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL ITEMS REQUIRED FOR A COMPLETE AND ACCEPTABLE WORKING INSTALLATION PER CODE. THE ELECTRICAL CONTRACTOR IS RESPONSIBLE TO PROVIDE A FUNCTIONING SYSTEM AND SHALL COORDINATE WITH ARCHITECT/OWNER TO FIELD VERIFY INSTALLATION FOR OUTLETS, LIGHTING FIXTURES AND ELECTRICAL EQUIPMENT.
5. ALL MATERIAL SHALL BEAR UL LABEL WHERE APPLICABLE. THE CONTRACTOR SHALL FURNISH ALL LABOR, MATERIALS AND EQUIPMENT FOR A COMPLETE INSTALLATION. ALL MOUNTING HARDWARE AND WIRING HARDWARE SHALL BE FURNISHED BY THE CONTRACTOR.
6. ALL WIRING SHALL BE COPPER (CU), THWN INSULATION, 75°C. WHERE IT DOES NOT SPECIFIED, THE CONDUCTOR MATERIAL AND SIZES GIVEN IN THE PROJECT SHALL BE APPLIED TO COPPER WIRES. IF OTHER MATERIALS WILL BE USED, THE SIZE SHALL BE ADJUSTED ACCORDINGLY.
7. ALL CIRCUIT BREAKERS SHALL BE RATED MINIMUM 10,000 A.I.C.
8. ALL CONDUCTORS SHALL BE RUN IN CONDUITS UNLESS OTHER TYPES CAN BE USED AS PER NEC:
- A) PVC SCH-40 WHEN INSTALLED 12" UNDER SLABS ON GRADE OR WHEN EMBEDDED IN CONCRETE WALLS OR SLABS.
 - B) MC-CABLE CAN BE INSTALLED ACCORDING TO NEC 330.10 AND 330.12.
 - C) IMC WHEN INSTALLED CONCEALED IN MASONRY WALLS, DRY WALLS OR SUSPENDED CEILINGS, ALSO WHEN INSTALLED IN INTERIORS EXPOSED UP TO 8" AFF.
 - D) EMT INTERIORS EXPOSED ABOVE 8" AFF AND AT ANY HEIGHT IN ELECTRICAL, MECHANICAL AND TELECOMMUNICATION ROOMS.
 - E) NM-CABLE CAN BE INSTALLED WHEN PERMITTED BY 334.10.
9. IF PVC CONDUITS ARE USED FOR UNDERGROUND FEEDERS, AN EQUIPMENT GROUND CONDUCTOR SIZED PER NEC 250.122 MUST BE INSTALLED AND CONDUIT SIZE INCREASED AS REQUIRED.
10. CONTRACTOR TO VERIFY ADJUSTMENT FACTORS FOR MORE THAN THREE CURRENT-CARRYING CONDUCTORS IN A CONDUIT ACCORDING TO TABLE 310.15(b)(2)(a).
11. ELECTRICAL EQUIPMENT, SUCH AS SWITCHBOARDS, SWITCHGEAR, PANELBOARDS, INDUSTRIAL CONTROL PANELS, METER SOCKET ENCLOSURES, AND MOTOR CONTROL CENTERS, THAT ARE IN OTHER THAN DWELLING UNITS, AND ARE LIKELY TO REQUIRE EXAMINATION, ADJUSTMENT, SERVICING, OR MAINTENANCE WHILE ENERGIZED, SHALL BE FIELD ORATORY MARKED TO WARN QUALIFIED PERSONS OF "POTENTIAL ELECTRIC ARC FLASH HAZARDS". THE MARKING SHALL MEET THE REQUIREMENTS IN 110.21(B) AND SHALL BE LOCATED SO AS TO BE CLEARLY VISIBLE TO QUALIFIED PERSONS BEFORE EXAMINATION, ADJUSTMENT, SERVICING, OR MAINTENANCE OF THE EQUIPMENT (AS PER NEC 110.16).
12. SERVICE EQUIPMENT IN OTHER THAN DWELLING UNITS SHALL BE LEGIBLY MARKED IN THE FIELD WITH THE MAXIMUM AVAILABLE FAULT CURRENT. THE FIELD MARKING(S) SHALL INCLUDE THE DATE THE FAULT CURRENT CALCULATION WAS PERFORMED AND BE OF SUFFICIENT DURABILITY TO WITHSTAND THE ENVIRONMENT INVOLVED, AS PER NEC 110.24(A)
13. ALL ELECTRICAL EQUIPMENT SHALL BE INSTALLED ABOVE FLOOD ELEVATION LEVEL. VERIFY NGVD IN ARCH. PLANS PRIOR INSTALLATION.
14. WITH 30 DAYS AFTER THE DATE OF SYSTEM ACCEPTANCE, RECORD DRAWINGS OF THE ACTUAL INSTALLATION SHALL BE PROVIDED TO THE OWNER, INCLUDING A SINGLE LINE DIAGRAM OF BUILDING ELECTRICAL DISTRIBUTION SYSTEM AND FLOOR PLANS INDICATING LOCATION AND AREA SERVED FOR ALL DISTRIBUTION. ALSO, AN OPERATING AND MAINTENANCE MANUAL SHALL BE PROVIDED, INCLUDING SUBMITTAL DATA STATING EQUIPMENT RATING AND SELECTED OPTIONS FOR EACH PIECE OF EQUIPMENT REQUIRING MAINTENANCE.
15. A MINIMUM OF 90% OF THE LAMPS IN PERMANENTLY INSTALLED LIGHT FIXTURES SHALL BE HIGH-EFFICACY LAMPS (AT LEAST 45 LUMENS-PER-WATT). PROVIDE FIXTURES WITH LAMPS. ALL RECESSED LIGHT FIXTURES IN CONTACT WITH INSULATION SHALL BE RATED FOR SUCH USE.
16. THE MEANS OF EGRESS ILLUMINATION LEVEL SHALL BE NOT LESS THAN 1 FC (11 LUX) AT THE WALKING SURFACE.




1 TIME SWITCH "T/S" DETAIL
E-1 SCALE: N.T.S.

ELECTRICAL SYMBOL LEGEND

- STRIP LED LIGHT FIXTURE
- PENDANT MOUNTED LED LIGHT FIXTURE
- WALL MOUNTED LIGHT FIXTURE (SCONCE)
- RECESSED MOUNTED LIGHT FIXTURE
- EMERGENCY BATTERY BACKUP (90 MIN) LIGHT FIXTURE
- EMERGENCY BATTERY BACKUP (90 MIN) EXIT SIGN FIXTURE
- EXHAUST FAN (BY OTHERS)
- SINGLE LIGHTING SWITCH AT 48" AFF
- SINGLE LIGHTING SWITCH, DIMMERABLE, AT 48" AFF
- OCCUPANCY SENSOR, WALL MOUNTED
- DUPLEX RECEPTACLE 20A, 125V, AT 18" AFF
- DUPLEX RECEPTACLE 20A, 125V, AT 44" AFF
- DUPLEX RECEPTACLE 20A, 125V, FLOOR MOUNTED
- SINGLE RECEPTACLE 20A, 125V, AT 18" AFF
- QUADPLEX RECEPTACLE 20A, 125V, AT 18" AFF
- DUPLEX RECEPTACLE 20A, 125V, CEILING MOUNTED
- TELEPHONE/DATA OUTLET AT 18" AFF
- TV OUTLET AT 18" AFF
- DISCONNECT SWITCH
- ELECTRICAL PANEL
- (D) DENOTE DIMMER
- GFI GROUND FAULT CURRENT INTERRUPTER
- WP DENOTE "WEATHERPROOF" FIXTURE

KEYNOTES


- 1 CONNECT ALL EXIT SIGNS AND BATTERY PACKS IN EMERGENCY LIGHT FIXTURES AHEAD OF ANY LIGHTING CONTROL DEVICE FOR CONTINUOUS OPERATION OF THE BATTERY CHARGER. LIGHT FIXTURES WITH BATTERY BACKUP SHALL BE EASILY IDENTIFIABLE BY MEANS APPROVED BY FIRE INSPECTOR.
- 2 ADJUST FOCUS OF ALL RECESSED DIRECTIONAL LIGHTING TO FULLY ILLUMINATE MENU BOARDS, MERCHANDISE BAYS AND ARTWORK.
- 3 ALL FIXTURES IN AREAS WHERE EXPOSED FOOD, CLEAN EQUIPMENT OR UTENSILS, OR UNWRAPPED SINGLE SERVICE ITEMS WILL BE EXPOSED, SHALL HAVE SHATTERPROOF LAMPS IF THE FIXTURE IS NOT LEASED. ARCHITECT TO INCLUDE APPROPRIATE LAMPS/FIXTURES ON DRAWINGS AND SCHEDULES AND COMPLY WITH ANY ADDITIONAL JURISDICTIONAL LIGHTING REQUIREMENT.
- 4 WHEN REQUIRED, BALLAST BOXES, TRANSFORMERS, JUNCTION BOXES AND ASSOCIATED WIRING FOR LIGHT FIXTURES SHALL BE INSTALLED HIDDEN FROM VIEW.
- 5 PROVIDE NEMA 3R ENCLOSURE FOR ELECTRICAL EQUIPMENT LOCATED IN EXTERIORS. PROVIDE FUSES IF REQUIRED.
- 6 ALL DATA AND TELEPHONE DEVICES TO BE LOCATED AT 18" AFF UNLESS OTHERWISE NOTED. PROVIDE WALL BOX AND 3/4" EMPTY CONDUIT WITH PULL STRING TO 6" ABOVE CEILING. CABLING, JACK AND TERMINATION BY CLIENT'S IT-VENDOR (TYP.)
- 7 OUTDOOR RECEPTACLES TO BE GFCI/WR/WP WHILE IN-USE. PROVIDE COVER APPROVED FOR THE LOCATION.
- 8 PROVIDE SHUNT TRIP BREAKERS IN PANEL FOR CIRCUITS OF EQUIPMENT UNDER HOOD (IF ANY). SHUNT TRIP OPERATION TO BE CONTROLLED BY ANSUL SYSTEM.



RISER DIAGRAM
(N.T.S.)

PANEL "A"																					
TYPE: SIEMENS OR EQUAL APPROVED						RATED VOLTAGE: 120/208V, 3PH, 4W						MAINS: M.L.O.									
MOUNTING: SURFACE						BUS RATING: 400						AMPS					FEED LOCATION: TOP				
ENCLOSURE: NEMA 1						A.I.C. RATING: 22						KAIC					SYSTEM: NORMAL				
SUPPLY FROM: UTILITY COMPANY						BRANCH POLES: 42						CIRCUITS					LOCATION: SEE FLOOR PLAN				
ID	LOAD SERVED	COND.	EQ. GND.	WIRE AWG	TYPE	TRIP [A]	CKT	Phase A [kVA]	Phase B [kVA]	Phase C [kVA]	CKT	TRIP [A]	TYPE	WIRE AWG	EQ. GND.	COND.	LOAD SERVED	ID			
L	ITG. SALON	1/2"	12	12	-	20	1	0.6	0.9			2							C		
L	ITG. SALON	1/2"	12	12	-	20	3		0.4	0.9		4	20/2	-	12	12	3/4"	WALK-IN COOLER EVAP. UNIT	C		
L	ITG. CORRIDOR	1/2"	12	12	-	20	5			0.8	1.6	6	30/2	-	10	10	3/4"	WALK-IN COOLER COND. UNIT	C		
L	ITG. BATH	1/2"	12	12	-	20	7	0.2	1.6			8	10	20	-	12	12	1/2"	WALK-IN COOLER DOOR DEFROST	K	
L	ITG. EXTERIOR	1/2"	12	12	TS	20	9		0.2	1.2		10	20	-	12	12	1/2"	WALK-IN COOLER DOOR DEFROST	K		
L	ITG. BAR	1/2"	12	12	-	20	11			0.9	0.9	12	20/2	-	12	12	3/4"	KCF-1	O		
L	ITG. DISHWASHER AREA	1/2"	12	12	-	20	13	0.3	0.9			14							O		
R	RECEP. BATH	3/4"	12	12	-	20	15		0.5	0.9		16	20/2	-	12	12	3/4"	KSF-1	O		
R	RECEP. SALON	3/4"	12	12	-	20	17			0.7	0.9	18							O		
R	RECEP. SALON	3/4"	12	12	-	20	19	0.7	0.5			20	20	GF	12	12	1/2"	GAS WATER HEATER	K		
R	RECEP. BAR	3/4"	12	12	-	20	21		1.1	0.5		22	20	GF	12	12	1/2"	GAS WATER HEATER	K		
K	ICE MACHINE	3/4"	12	12	GF	20	23			0.7	7.1	24							N		
R	RECEP. BAR	3/4"	12	12	-	20	25	0.2	7.1			26	100/3	-	3	8	1-1/4"	CU-1	N		
R	RECEP. COUNTER TOP BAR	3/4"	12	12	-	20	27		1.5	7.1		28							N		
O	BOTTLE COOLER	3/4"	12	12	GF	20	29			0.7	0.9	30	20	-	12	12	1/2"	RECEP. GEN. CONV.	R		
O	TABLE SANDWICH	3/4"	12	12	GF	20	31	0.9	0.5			32	20	GF	12	12	1/2"	RECEP. IGNITION GAS EQUIPMENT	K		
O	TABLE SANDWICH	3/4"	12	12	GF	20	33		0.9	0.5		34	20	-	12	12	1/2"	RECEP. GEN. CONV.	R		
K	DISHWASHER	3/4"	12	12	GF	30	35			2.7	0.4	36	20	-	12	12	1/2"	RECEP. RECEPTION	R		
N	HAND DRYER	1/2"	12	12	GF	20	37	(NC)	1.2			38	20	-	12	12	1/2"	RECEP. SHOW WINDOWS	R		
N	HAND DRYER	1/2"	12	12	GF	20	39		(NC)	1.2		40	20	-	12	12	1/2"	RECEP. SHOW WINDOWS	R		
O	TIME SWITCH CONTROLLER	1/2"	12	12	-	20	41			0.1	1.2	42	20	-	12	12	1/2"	RECEP. SHOW WINDOWS	R		
R	RECEP. ON THE ROOF	1/2"	12	12	-	20	43	1.5	1.5			44	20	-	12	12	1/2"	RECEP. EXTERIOR	R		
	SPACE	-	-	-	-	-	45					46	-	-	-	-	-	SPACE			
	SPACE	-	-	-	-	-	47					48	-	-	-	-	-	SPACE			
	SPACE	-	-	-	-	-	49	-	-			50	-	-	-	-	-	SPACE			
	SPACE	-	-	-	-	-	51					52	-	-	-	-	-	SPACE			
	SPACE	-	-	-	-	-	53					54	-	-	-	-	-	SPACE			
							79	-	14.2			56							C		
							81		-	14.2		58	150/3	-	1/0	6	2"	AHU-1	C		
							83			-	14.2	60							C		
								32.8	31.1	33.8											
ID: (R) RECEPTACLE LOAD (L) LIGHTING LOAD (O) OTHER LOAD (C) A/C (COLD OR HEAT)																					
DEMAND LOAD CALCULATION:																					
TOTAL CONNECTED LOAD: = 97.7 kVA																					
RECEP. LOAD = 33.1 kVA																					
1ST 10 kVA @ 100% = 10.0 kVA																					
REMAINING @ 50% = 1.6 kVA																					
KITCHEN LOADS @ 65% = 4.0 kVA																					
LIGHTING LOADS @ 125% = 4.3 kVA																					
OTHER LOADS @ 100% = 6.2 kVA																					
TOTAL kVA A/C LOADS @ 100% = 47.6 kVA																					
TOTAL NON CONCURRENT LOADS = 21.3 kVA																					
TOTAL DEMAND LOAD: = 73.6 kVA																					
DEMAND AMPERES = 284 AMP'S																					

ALL WORK SHALL BE PERFORMED BY A LICENSED CONTRACTOR. CONTRACTOR IS TO PROVIDE ALL MATERIALS AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE SYSTEMS INDICATED ON THE DRAWINGS AS SPECIFIED AND AS REQUIRED BY ALL APPLICABLE CODES, ORDINANCES, AND AHJ.



ALL WORK SHALL BE PERFORMED BY A LICENSED CONTRACTOR. CONTRACTOR IS TO PROVIDE ALL MATERIALS AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE SYSTEMS INDICATED ON THE DRAWINGS AS SPECIFIED AND AS REQUIRED BY ALL APPLICABLE CODES, ORDINANCES, AND AHJ.

RESTAURANT
RENOVATION


Address: 190 Spruce Ln
Gatlinburg , Tennessee

PROJECT NO.
02222
DATE
08/22/2022
REVISIONS



SHEET NO

E-2



Lighting Floor Plan
Scale: 1/4" = 1'-0"

ALL WORK SHALL BE PERFORMED BY A LICENSED CONTRACTOR. CONTRACTOR IS TO PROVIDE ALL MATERIALS AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE SYSTEMS INDICATED ON THE DRAWINGS AS SPECIFIED AND AS REQUIRED BY ALL APPLICABLE CODES, ORDINANCES, AND AHJ.


RESTAURANT RENOVATION
Address: 190 Spruce Ln
Gallatinburg, Tennessee

PROJECT NO.
02222
DATE
08/22/2022
REVISIONS



SHEET NO

E-3



Roof Electrical Plan

Scale: 1/4" = 1'-0"



ALL WORK SHALL BE PERFORMED BY A LICENSED CONTRACTOR. CONTRACTOR IS TO PROVIDE ALL MATERIALS AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE SYSTEMS INDICATED ON THE DRAWINGS AS SPECIFIED AND AS REQUIRED BY ALL APPLICABLE CODES, ORDINANCES, AND AHJ.

RESTAURANT RENOVATION	Address: 190 Spruce Ln Gallatinburg , Tennessee
PROJECT NO. 02222 DATE 08/22/2022 REVISIONS	PROFESSIONAL ENGINEER TAYLOR HEIM STATE OF TENNESSEE No. 197601 04-18-23
SHEET NO E-4	

MECHANICAL SPECIFICATIONS

1.0 GENERAL

1.1 SCOPE OF WORK

A. THE WORK UNDER THIS SECTION OF THE SPECIFICATIONS INCLUDES ALL RELATED LABOR, MATERIALS, AND EQUIPMENT AS DELINEATED ON THESE CONTRACT DRAWINGS AND RELATED DOCUMENTS. WORK SHALL BE IN ACCORDANCE WITH THESE SPECIFICATIONS AND THE CONTRACT DRAWINGS AND SUBJECT TO THE TERMS AND CONDITIONS OF THE CONTRACT.

THE MECHANICAL CONTRACTOR SHALL BE RESPONSIBLE WITH COORDINATING WITH GC AND OTHER TRADES FOR MECHANICAL EQUIPMENT CONNECTIONS. CONTROLS WORK SHALL BE THE RESPONSIBILITY OF THE MECHANICAL CONTRACTOR. PROVIDING A CRANE FOR THE REMOVAL OF ROOF TOP EXISTING EQUIPMENT AND INSTALLATION OF NEW HVAC EQUIPMENT SHALL BE THE RESPONSIBILITY OF THE MECHANICAL CONTRACTOR.

B. THE GENERAL SCOPE OF WORK CONSISTS OF, BUT IS NOT LIMITED TO, THE FOLLOWING:

- DEVELOPMENT OF DETAILED PROJECT CONSTRUCTION SCHEDULE AND COORDINATION OF WORK WITHIN THREE WEEKS OF BEING AWARDED THE CONTRACT.
- RIGGING INTO PLACE RTUs, FANS AND OTHER EQUIPMENT. THIS INCLUDES ANY NECESSARY GAS PIPING AS WELL AS ANY G.C. WORK NECESSARY TO OPEN AND CLOSE UP WALLS OR ROOFS. RIGGING SHALL BE SUBCONTRACTED TO THE BUILDING'S PREFERRED RIGGING COMPANY.
- INSTALLING SCHEDULED AC EQUIPMENT.
- FURNISH AND INSTALL NEW DUCTS AND DISTRIBUTION WITH SUPPLY OUTLETS.
- INSTALLATION OF SPLIT SYSTEM WITH ASSOCIATED REFRIGERANT PIPING.
- PROCURING AND INSTALLING NEW PIPING, VALVES AND APPURTENANCES.
- PREPARING AND SUBMITTING RECORD AS-BUILT DRAWINGS AND OPERATING AND MAINTENANCE MANUALS FOR EQUIPMENT PROVIDED BY THIS CONTRACTOR.
- CONDUCTING AIR SYSTEMS BALANCING AND SUBMITTING REPORTS.
- INSULATION OF ALL PIPING AS REQUIRED.
- SUBCONTRACTING THE BUILDING CONTROLS CONTRACTOR FOR INSTALLATION OF NEW CONTROLS.
- OTHER WORK AS DELINEATED IN THE CONTRACT DRAWINGS, INCLUDING ALL ELECTRICAL WORK FOR 15 TON AC SYSTEM AND ALL OTHER PROPOSED MECH EQUIPMENTS.

1.2 BIDDING

A. CONTRACTOR SHALL VISIT THE JOB AND FULLY FAMILIARIZE THEMSELVES WITH THE EXISTING CONDITIONS PRIOR TO SUBMISSION OF BIDS.

B. CONTRACTOR SHALL COORDINATE THE REQUIREMENTS OF ANY AND ALL DRAWINGS INCLUDING MECHANICAL, ELECTRICAL, AND CONTROLS. ANY CONFLICT SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER DURING THE BIDDING PERIOD.

C. CONTRACTOR TO OBTAIN A COPY OF THE BUILDING RULES AND REGULATIONS PRIOR TO BID SUBMISSION TO DETERMINE THE REQUIREMENTS AND THE EXTENT OF PREMIUM TIME WORK REQUIRED BY THE BUILDING.

1.3 GENERAL REQUIREMENTS

A. ALL WORK SHALL BE IN ACCORDANCE WITH ALL APPLICABLE STATE OF TENNESSEE BUILDING CODES.

B. CONTRACTOR SHALL PAY ALL FEES AND TAXES, OBTAIN ALL PERMITS AND APPROVALS, FILE THE REQUIRED DOCUMENTS, SCHEDULE AND PAY ALL FEES FOR ALL BUILDING INSPECTIONS AND FINAL SIGN-OFF INSPECTIONS.

C. CONTRACTOR SHALL COORDINATE WITH OTHER CONTRACTORS INCLUDING, ELECTRICAL.

D. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ANY WALL OR ROOF PENETRATIONS FOR NEW DUCT OR PIPING WORK AND SHALL PATCH AND REPAIR, TO MATCH EXISTING, ALL HOLES, ACCESS OPENINGS, ETC. DUE TO NEW WORK. ALL PENETRATIONS SHALL BE PATCHED AND FIRESTOPPED AS REQUIRED TO MAINTAIN THE INTENDED FIRE RATING. UNLESS NOTED OTHERWISE ALL FLOORS AND MECHANICAL ROOM WALLS SHALL BE CONSIDERED TO BE 2-HOUR RATED.

E. CONTRACTOR SHALL INFORM ENGINEER IMMEDIATELY UPON DISCOVERY OF ANY ASBESTOS OR OTHER HAZARDOUS MATERIAL THAT WILL BE DISTURBED DUE TO THIS WORK.

F. DEMOLITION AND OTHER WORK WHICH MAY CREATE A DISTURBANCE MUST BE COORDINATED WITH THE GC. THE DELIVERY, HANDLING AND INSTALLATION OF MATERIALS, EQUIPMENT AND REMOVAL OF DEBRIS MUST BE ARRANGED TO AVOID ANY INCONVENIENCE AND ANNOYANCE TO OWNER. THE CONTRACTOR SHALL DISPOSE OF ALL DEMOLISHED AND UNUSED MATERIALS.

G. THOROUGHLY BRUSH AND CLEAN UP WORK AT THE END OF EACH DAY. REMOVE ALL DEBRIS FROM INSIDE AND OUTSIDE OF ALL DUCTWORK, PIPING AND EQUIPMENT.

H. SUBSTITUTIONS FOR THE SPECIFIED EQUIPMENT SHALL NOT BE PERMITTED WITHOUT APPROVAL FROM THE ENGINEER. THE ASSOCIATED CHANGE IN THE CONTRACT PRICE SHALL BE INCLUDED WITH ANY PROPOSED SUBSTITUTIONS.

I. SEISMIC MOUNTING AND BRACING OF ALL EQUIPMENT, PIPING ETC. SHALL BE IN ACCORDANCE WITH STATE AND LOCAL REQUIREMENTS. THE SEISMIC REQUIREMENTS SHALL BE BASED ON SEISMIC ZONE.

J. THE CONTRACTOR SHALL COORDINATE WITH EQUIPMENT MANUFACTURER'S SERVICE REPRESENTATIVE TO ENSURE PROPER INSTALLATION, PIPING AND SERVICE CLEARANCE REQUIREMENTS ARE MET.

K. LAYOUT SYSTEMS TO MAINTAIN ACCESS AND SERVICE CLEARANCES FOR INSTALLED EQUIPMENT, VALVES, CONTROLS, VOLUME DAMPERS AND ALL COMPONENTS REQUIRING ACCESS. SERVICE ACCESS SHALL BE AS RECOMMENDED BY MANUFACTURER OR AS REQUIRED BY CODE WHICHEVER IS GREATER.

L. MAINTAIN OPERATION OF BUILDING SYSTEMS DURING CONSTRUCTION, ANY REQUIRED SHUTDOWNS OF BUILDING SYSTEMS MUST BE COORDINATED WITH THE OWNER.

M. CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND OPERATION OF ALL SYSTEMS UNTIL THE FINAL ACCEPTANCE OF THE WORK.

N. UNLESS OTHERWISE SPECIFIED, THE MOST RECENT VERSIONS OF THE FOLLOWING CODES AND STANDARDS APPLY AND ARE MADE A PART OF THIS SPECIFICATION

- STATE OF TENNESSEE BUILDING CODES
 - UNDERWRITER'S LABORATORIES, INC. (UL).
 - NATIONAL FIRE PROTECTION ASSOCIATION (NFPA).
 - AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME).
 - AMERICAN NATIONAL STANDARD INSTITUTE (ANSI).
 - OSHA – FEDERAL STANDARDS
 - AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR CONDITIONING ENGINEERS, INC. (ASHRAE).
 - AIR CONDITIONING & REFRIGERATION INSTITUTE (ARI).
 - AMERICAN WELDING SOCIETY (AWS).
 - AMERICAN SOCIETY OF TESTING AND MATERIALS (ASTM).
- O. PATCH, FILL AND REPAIR, INCLUDING PAINTING OR RECOVERING ALL SURFACES DISTURBED, CUT, DAMAGED, IN NEED OF REPAIR OR MADE IMPERFECT BY ALTERATIONS OR REMOVAL WORK AND AS REQUIRED.

1.4 COORDINATION WITH BUILDING MANAGEMENT

A. THIS CONTRACTOR IS RESPONSIBLE FOR ADHERING TO THE BUILDING OWNER'S RULES AND REGULATIONS. ANY DISCREPANCIES BETWEEN THE CONTRACTOR DOCUMENTS AND THE BUILDING RULES AND REGULATIONS SHALL BE SUBMITTED IN WRITING TO THE ARCHITECT/ENGINEER FOR REVIEW, WITH BID SUBMISSION.

B. COORDINATE WITH BUILDING OWNER FOR ANY SERVICE INTERRUPTION OF EXISTING SYSTEMS AND GIVE NOTICE AS REQUIRED BY BUILDING RULES AND REGULATIONS OR A MINIMUM OF TWO (2) DAYS PRIOR TO ANY WORK, WHICHEVER IS MORE STRINGENT. CONTRACTOR IS TO PERFORM WORK ON PREMIUM TIME, IF SO DIRECTED BY BUILDING OWNER, SO AS NOT TO INTERRUPT BUILDING SERVICES DURING OCCUPIED PERIODS.

1.5 SUBMITTALS

A. SHOP DRAWINGS OF THE FOLLOWING SHALL BE SUBMITTED FOR REVIEW PRIOR TO PURCHASE AND INSTALLATION.

- MANUFACTURER'S SUBMITTAL DATA FOR ALL EQUIPMENT SUPPLIED. SUBMITTALS SHALL CLEARLY INDICATE SPECIFIC ITEMS PROPOSED AND WHERE EACH ITEM IS TO BE APPLIED.
- EQUIPMENT SOUND POWER DATA BROKEN INTO OCTAVE BANDS.
- DIMENSIONED AND DETAILED PIPING, EQUIPMENT AND DUCTWORK LAYOUT.
- SHOP STANDARDS AND INSTALLATION DETAILS FOR DUCTWORK, PIPING, INSULATION, STRUCTURAL SUPPORTS, VIBRATION ISOLATION, PIPE CLEANING AND FLUSHING PROCEDURE.
- AIR BALANCING REPORTS.
- TEMPERATURE CONTROLS SUBMITTAL INCLUDING FLOW DIAGRAMS, WIRING DIAGRAMS, PRODUCT DATA, SEQUENCE OF OPERATION AND ALL CONTROL POINTS.
- OTHER SUBMITTAL DATA NOTED ELSEWHERE.

B. SUBMITTALS SHALL BE IN "PDF" FORMAT AND SUBMITTED TO THE PROJECT TEAM (IF TO BE ISSUED AT CONTRACT AWARD).

C. SUBMIT DETAILED PROJECT SCHEDULE, WITHIN TWO (2) WEEKS OF CONTRACT AWARD.

1.6 RECORD DRAWINGS

A. SUBMIT INFORMATION FOR ALL INSTALLED EQUIPMENT INCLUDING: OPERATING AND MAINTENANCE MANUALS, START-UP REPORTS, SPARE PARTS LISTS.

B. AS-BUILT DRAWINGS SHOWING ALL DUCTWORK, PIPING AND EQUIPMENT AND TEST AND BALANCING REPORTS SHALL BE SUBMITTED TO THE OWNER AT THE COMPLETION OF THE WORK. THE AS-BUILT DRAWINGS SHALL ALSO SHOW EXISTING WORK WITHIN THE WORK AREA INCLUDING DUCTS AND PIPING THAT WAS CAPPED, REROUTED AND REMAINING IN WORK AREA.

C. CONTROL SYSTEM AS-BUILT AND OPERATING MANUAL.

D. RECORD DOCUMENTS TO BE ISSUED IN "PDF" AND TWO PRINTED COPIES.

1.7 MECHANICAL CONTRACTOR COMMISSIONING RESPONSIBILITIES

THE MECHANICAL CONTRACTOR SHALL:

- FACILITATE THE COORDINATION OF THE COMMISSIONING WORK BY THE CXA WITH ALL SUB-CONTRACTORS AND THE OWNER.
- INCLUDE THE COST OF COMMISSIONING IN THE TOTAL CONTRACT PRICE.
- FURNISH A COPY OF ALL CONSTRUCTION DOCUMENTS, ADDENDA, CHANGE ORDERS AND APPROVED SUBMITTALS AND SHOP DRAWINGS (IF APPLICABLE) RELATED TO COMMISSIONED EQUIPMENT TO THE CXA.
- IN EACH PURCHASE ORDER OR SUBCONTRACT WRITTEN, INCLUDE REQUIREMENTS FOR COMMISSIONING TASKS.
- PROVIDE ALL NECESSARY STAFF, TOOLS AND INSTRUMENTATION AND COORDINATION REQUIRED FOR THE COMMISSIONING WORK.
- ENSURE THAT ALL SUBS EXECUTE THEIR COMMISSIONING RESPONSIBILITIES ACCORDING TO THE CONTRACT DOCUMENTS AND SCHEDULE.
- A REPRESENTATIVE SHALL ATTEND A COMMISSIONING SCOPING MEETING AND OTHER NECESSARY MEETINGS SCHEDULED BY THE CXA TO FACILITATE THE CXA PROCESS.
- COMPLETE ALL CONSTRUCTION CHECKLISTS INCLUDING MANUFACTURER'S CHECK, TEST AND START-UP DOCUMENTATION.

1.8 START-UP AND TRAINING

A. CONTRACTOR TO PROVIDE OWNER TRAINING IN THE OVERALL OPERATION AND MAINTENANCE OF ALL INSTALLED SYSTEMS.

B. ENGAGE THE SERVICES OF MANUFACTURERS SUPPLYING THE EQUIPMENT FOR THE EQUIPMENT STARTUP AND TO INSTRUCT THE OWNER'S PERSONNEL IN THE PROPER OPERATION AND SERVICING OF THE SYSTEM.

1.9 GUARANTEE

A. ALL MATERIALS AND WORKSMANSHIP SHALL BE GUARANTEED FOR A PERIOD OF ONE YEAR FROM DATE OF FINAL ACCEPTANCE OF THIS WORK. FINAL ACCEPTANCE SHALL BE DEFINED AS THE TIME AT WHICH THE MECHANICAL WORK IS TAKEN OVER AND ACCEPTED BY THE OWNER, AND IS UNDER CARE, CUSTODY, AND CONTROL OF THE OWNER. ENGAGE THE SERVICES OF VARIOUS MANUFACTURERS SUPPLYING THE EQUIPMENT FOR THE PROPER STARTUP AND OPERATION OF ALL SYSTEMS INSTALLED. INSTRUCT THE OWNER'S PERSONNEL IN THE PROPER OPERATION AND SERVICING OF THE SYSTEM.

B. THE CONTRACTOR SHALL GUARANTEE TO REPLACE OR REPAIR PROMPTLY AND ASSUME RESPONSIBILITY FOR ALL EXPENSES INCURRED FOR ANY WORKMANSHIP AND EQUIPMENT IN WHICH DEFECTS DEVELOP WITHIN THE GUARANTEE PERIOD. THIS WORK SHALL BE DONE AS DIRECTED BY THE OWNER. THIS GUARANTEE SHALL INCLUDE RESPONSIBILITY FOR ALL EXPENSES INCURRED IN REPAIRING AND REPLACING WORK OF OTHER TRADES AFFECTED BY DEFECTS, REPAIRS OR REPLACEMENTS, IN EQUIPMENT SUPPLIED BY THIS CONTRACTOR.

C. ALL EQUIPMENT WARRANTIES SHALL BE TRANSFERRED TO OWNER AND SERVICED BY CONTRACTOR AS PART OF THIS CONTRACT.

D. ALL AIR CONDITIONING UNIT COMPRESSORS AND REFRIGERATION COMPONENTS SHALL HAVE A 5-YEAR WARRANTY.

2.0 DUCTWORK MATERIALS AND INSTALLATIONS

2.1 DUCTWORK

A. ALL DUCTWORK SHALL BE LOCK FORMING QUALITY GALVANIZED STEEL SHEETS UNLESS OTHERWISE NOTED ON DRAWINGS. ALL DUCTWORK SHALL CONFORM TO THE CONSTRUCTION DETAILS AND RECOMMENDATIONS IN THE LATEST ISSUES OF THE ASHRAE GUIDE, NFPA BULLETIN'S 90A, B & C AND THE SMACNA DUCT MANUAL. INSTALLATION OF DUCTWORK SHALL BE AS RECOMMENDED BY THE ABOVE. ALL DUCT SEAMS SHALL BE SEALED WITH DUCT SEALANT. DUCT LEAKAGE SHALL NOT EXCEED VALUES SET BY THE SMACNA STANDARDS, AND RECOMMENDATIONS BY ASHRAE, AND IN NO CASE SHALL BE MORE THAN 5 PERCENT.

C. PRESSURE CLASSIFICATIONS SHALL BE MINIMUM OF 2" W.G. EXCEPT AS INDICATED BELOW AND AS INDICATED ON DRAWINGS. ALL SYSTEM COMPONENTS SHALL BE SELECTED AND INSTALLED TO ACHIEVE THE PRESSURE RATINGS:

SERVICE	PRESSURE RATING
DUCTWORK BETWEEN THE AIR HANDLING UNIT DISCHARGE AND ISOLATION AND SMOKE/FIRE DAMPERS.	3" IN. W.G.

DUCTWORK DOWNSTREAM OF VAV BOX, BRANCH DUCTS TO SINGLE DIFFUSERS

1" IN. W.G.

D. THE CONTRACTOR SHALL PROVIDE BALANCING DAMPERS, AS SHOWN ON THE PLANS AND AS REQUIRED TO ACHIEVE SMOOTH AIR FLOW.

E. ALL 90 DEGREE MITER ELBOWS SHALL HAVE DOUBLE THICKNESS AIR FOIL TYPE TURNING VANES AS DETAILED IN THE SMACNA STANDARDS. ALL OTHER ELBOWS SHALL HAVE A MINIMUM TURNING RADIUS OF ONE DUCT WIDTH AS MEASURED FROM CENTER LINE. ALL DUCT SUPPORTS SHALL CONFORM TO SMACNA STANDARDS.

F. DUCT DIMENSIONS SHOWN ON DRAWINGS SHALL BE CLEAR INSIDE DIMENSIONS.

2.2 AUTOMATIC DAMPERS

A. PROVIDE AUTOMATIC DAMPERS AS INDICATED ON CONTRACT DRAWINGS.

B. DAMPERS TO BE LOW LEAKAGE TYPE, WITH PUBLISHED LEAKAGE DATA CERTIFIED UNDER THE AMCA CERTIFIED RATING PROGRAM SHOWING LEAKAGE THROUGH A 48 INCH BY 48 INCH DAMPER AT 4 INCH WATER GAUGE PRESSURE DIFFERENCE TO BE LESS THAN 10 CFM PER SQUARE FOOT.

C. AUTOMATIC DAMPERS SHALL BE THE PARALLEL OR OPPOSED BLADE TYPE AS SPECIFIED BELOW OR AS NOTED ON THE DRAWINGS.

- OTHER MODULATING AND MIXING DAMPERS SHALL BE OPPOSED BLADE CONFIGURATION.
- TWO-POSITION SHUTOFF DAMPERS MAY BE PARALLEL OR OPPOSED BLADE.

D. DAMPER FRAMES SHALL BE 13 GAUGE GALVANIZED STEEL CHANNEL OR 1/8 INCH EXTRUDED ALUMINUM WITH REINFORCED CORNER BRACING. DAMPER BLADES SHALL BE NOT LESS THAN 16 GAUGE.

E. DAMPERS TO HAVE A MAXIMUM BLADE LENGTH OF 48 INCHES AND A MAXIMUM BLADE WIDTH OF 8 INCHES. THE MAXIMUM HEIGHT OF EACH DAMPER SECTION SHALL BE 12 INCHES. WHERE GREATER LENGTH OR HEIGHT IS REQUIRED, USE MULTIPLE DAMPER SECTIONS. DAMPERS TO HAVE EXTERNAL SHAFT TYPE UNLESS NOTED OR APPROVED OTHERWISE. DAMPERS SHALL HAVE EXPOSED LINKAGES.

F. DAMPER SHAFT BEARINGS SHALL BE AS RECOMMENDED BY THE MANUFACTURER FOR THE APPLICATION, OIL IMPREGNATED SINTERED BRONZE OR BETTER.

G. ALL BLADE EDGES AND TOP AND BOTTOM OF THE FRAME SHALL BE PROVIDED WITH REPLACEABLE BUTYL RUBBER OR NEOPRENE SEALS. SIDE SEALS SHALL BE SPRING LOADED STAINLESS STEEL BLADES AND SEALS SHALL BE SUITABLE FOR WIDE OPEN FACE VELOCITY OF UP TO 2000 FPM.

H. INSTALL DAMPER ACTUATORS OF SUFFICIENT QUANTITY AND SIZE TO LIMIT LEAKAGE TO SPECIFIED RATE AND BE SUITABLE FOR DESIGN FLOW AND PRESSURE CONDITIONS. DAMPER ASSEMBLIES CONSISTING OF MULTIPLE DAMPER SECTIONS TO BE PROVIDED WITH AT LEAST ONE DAMPER ACTUATOR PER SECTION OR BE CONNECTED WITH AN APPROVED JACK SHAFING ARRANGEMENT.

2.3 FIRE AND FIRE SMOKE DAMPERS

A. COMBINATION FIRE SMOKE DAMPERS SHALL BE UL 555S, AIRFOIL BLADE RUSKIN FSD-60 OR EQUIVALENT EQUAL. 120VAC ELECTRIC ACTUATOR LOCATE ACTUATOR TO MAINTAIN 24" MINIMUM ACCESS. USE OUT OF WALL TYPE AS SHOWN ON PLANS OR REQUIRED FOR ACCESS.

2.4 DUCT AND AIR SYSTEMS INSULATION

A. DUCTWORK INSULATION SHALL CONFORM TO MAXIMUM FLAME SPREAD/SMOKE DEVELOPMENT/FUEL CONTRIBUTION RATINGS OF 25 FLAME SPREAD, 50 SMOKE DEVELOPED AND 50 FUEL CONTRIBUTED IN ACCORDANCE WITH ASTM E84, WITH K< VALUE OF 0.28 AT 75 DEGREES F. INSULATION SHALL PROVIDE CONTINUOUS VAPOR BARRIER AND JOINTS SHALL BE SECURED WITH PRESSURE SENSITIVE TAPE. MOISTURE RESISTANCE SHALL BE MIN E96, 1.3 PERM. MINIMUM DUCTWORK INSULATION R VALUES SHALL BE AS FOLLOWS:

SERVICE	R=VALUE/THICKNESS
CONDITIONED SUPPLY DUCTS WITHIN CONDITIONED SPACE	1-1/2"
DUCTS LOCATED OUTDOORS OR SUBJECT TO OUTSIDE CONDITIONS	2"

C. PROVIDE 1-1/2", 3.0 LBS/CF RIGID GLASS FIBER BOARD ON ALL OUTSIDE AIR DUCTS AND PLENUMS, MIXED AIR PLENUMS, AND SUPPLY DUCTS WITHIN MECHANICAL ROOMS AND OTHER EXPOSED LOCATIONS. PROVIDE 1-1/2", 1.5 LBS/CF FLEXIBLE GLASS FIBER WRAP ON ALL SUPPLY DUCTS IN CONCEALED BUT ACCESSIBLE LOCATIONS.

D. PROVIDE 1" CLOSED CELL ELASTOMERIC INTERNAL RIGID DUCT LINER FOR A MINIMUM OF 20 FEET DOWN STREAM OF AIR HANDLING UNITS AND OTHER LOCATIONS WHERE INDICATED ON THE DRAWINGS. LINED SUPPLY DUCTWORK DOES NOT REQUIRE EXTERNAL DUCT INSULATION. AP/ARMAFLEX "GRAY" INSTALLED PER SMACNA STANDARDS.

E. PROVIDE 1", 1-1/2 LBS/CF, INTERNAL RIGID DUCT LINER FOR A MINIMUM OF 15 FEET UPSTREAM (RETURN) OF RETURN FANS AND AIR HANDLING UNITS AND OTHER LOCATIONS WHERE INDICATED ON THE DRAWINGS.

F. INSULATION SHALL BE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS AND SMACNA GUIDELINES.

2.5 AIR SYSTEM – VIBRATION ISOLATION

A. PROVIDE VIBRATION ISOLATION FOR ALL FANS WHERE NOT INTERNALLY ISOLATED.

B. WHERE FANS ARE NOT PROVIDED WITH INTERNALLY ISOLATED FANS –APPROVIDE NEOPRENE FLEXIBLE CONNECTIONS IN DUCTWORK AT FAN CONNECTIONS TO DUCTWORK.

C. AHUS SHALL BE SET ON NEOPRENE VIBRATION ISOLATION PADS.

2.6 LOUVERS

A. PROVIDE HIGH PERFORMANCE LOUVERS FOR INTAKE AND EXHAUST. 0.081 INCH EXTRUDED ALUMINUM CONSTRUCTION, 4" FRAME, 45 DEGREE BLADE, DRAINABLE DESIGN WITH WIRE MESH BIRD SCREEN. LOUVERS TO BE AMCA CERTIFIED WITH PERFORMANCE AS FOLLOWS FOR 48X48 SECTION:

MINIMUM FREE AREA: 50%
MAXIMUM PRESSURE DROP AT 700 FPM FREE AREA VELOCITY:
INTAKE: 0.10 INCH W.G.
EXHAUST: 0.09

MINIMUM FREE AREA VELOCITY FOR WATER PENETRATION: 1000 FPM

B. FINISH: MIL FINISH TO BE APPROVED BY ARCHITECT.

C. MANUFACTURERS: GREENHECK MODEL ESD-403, RUSKIN MODEL ELF445DX

3.0 PIPING MATERIALS AND INSTALLATION

3.1 GENERAL

A. PRESSURE RATINGS FOR PRESSURIZED PIPING SHALL BE AS INDICATED BELOW AND AS NOTED ON THE DRAWINGS. ALL SYSTEM MATERIALS AND COMPONENTS SHALL BE SELECTED AND INSTALLED TO ACHIEVE THE PRESSURE RATINGS AS FOLLOWS:

SERVICE	PRESSURE RATING
REFRIGERANT	350 PSI
OTHER PIPING	125 PSI

3.2 PIPE AND FITTINGS

A. PROVIDE PIPING AS INDICATED ON SCHEDULE BELOW AND INDICATED ON DRAWINGS.

SERVICE	PIPING	JOINTS
DOMESTIC WATER	TYPE L COPPER	SWEAT
AC CONDENSATE	TYPE M COPPER	SWEAT
AC REFRIGERANT	TYPE ACR COPPER	BRAZED

B. COPPER PIPING: WROUGHT COPPER FITTINGS. SWEAT JOINTS 95-5 TIN ANTIMONY SOLDER JOINTS. BRAZED JOINTS: _____

C. INSTALL ALL REFRIGERANT PIPING PER EQUIPMENT MANUFACTURERS SPECIFICATIONS.

3.3 VALVES AND PIPING SPECIALTIES

A. ALL VALVES SHALL BE OF A DESIGN WHICH THE MANUFACTURER LISTS FOR THE SERVICE AND SHALL BE OF MATERIALS ALLOWED BY THE LATEST EDITION OF THE ASME CODE FOR PRESSURE PIPING, FOR THE MAXIMUM OPERATING PRESSURE AND TEMPERATURE, UNLESS A HIGHER GRADE OR QUALITY IS HEREIN SPECIFIED. ALL VALVES SHALL BE OF THE SAME MANUFACTURER, EXCEPT FOR SPECIAL APPLICATIONS.

F. EACH VALVE SHALL HAVE THE MAKER'S NAME OR BRAND, THE FIGURE OR LIST NUMBER AND THE GUARANTEED WORKING PRESSURE CAST ON THE BODY AND CAST OR STAMPED ON THE BONNET, OR SHALL BE PROVIDED WITH OTHER MEANS OF EASY IDENTIFICATION.

G. PROVIDE VALVES AS INDICATED ON SCHEDULE BELOW AND INDICATED ON DRAWINGS.

SERVICE	VALVE	JOINTS
DOMESTIC WATER	BALL	

H. BALL VALVES UP TO 2-1/2 INCHES: BRONZE TWO PIECE BODY, STAINLESS STEEL FULL PORT BALL, TEFLON SEATS AND STUFFING BOX RING, LEVER HANDLE SOLDER ENDS.

I. PROVIDE EXTENDED SHAFT HANDLES FOR BALL VALVES WHERE INSULATION IS REQUIRED TO ALLOW INSULATION OF SPECIFIED THICKNESS TO BE INSTALLED.

J. BALL VALVES 3 INCHES AND UP:

K. BUTTERFLY VALVES: LUGGED DESIGN

L. GATE VALVES SHALL BE OF THE SOLID TAPERED WEDGE TYPE, UNION BONNET, RISING STEM.

M. FLOW LIMITING VALVES SHALL BE Y-BODY WITH REPLACEABLE INSERTS. MINIMUM OPERATING PRESSURE SHALL BE 2 PSI OR LESS. FLOW LIMITING VALVES SHALL BE ORISWOLD, HAYS OR APPROVED EQUAL.

N. CHECK VALVES INSTALLED IN THE HORIZONTAL POSITION SHALL BE SWING CHECKS; VALVES INSTALLED IN THE VERTICAL POSITION SHALL BE SILENT CHECKS, EXCEPT THAT ALL CHECK VALVES IN PUMP DISCHARGES SHALL BE SILENT CHECKS.

O. ALL VALVES 2 INCHES IN DIAMETER AND SMALLER SHALL BE ALL BRONZE WITH BRONZE BODIES. VALVES 2-1/2 INCHES IN DIAMETER AND LARGER SHALL HAVE IRON BODIES WITH BRONZE MOUNTINGS UNLESS OTHERWISE SPECIFIED.

P. ALL VALVES AND SPECIALTIES SHALL BE SO PLACED AS TO PERMIT EASY OPERATION AND ACCESS.

Q. ALL VALVES 2 INCHES IN DIAMETER AND SMALLER SHALL BE ALL BRONZE WITH BRONZE BODIES. VALVES 2-1/2 INCHES IN DIAMETER AND LARGER SHALL HAVE IRON BODIES WITH BRONZE MOUNTINGS UNLESS OTHERWISE SPECIFIED.

R. ALL VALVES UP TO 2 INCHES IN DIAMETER SHALL HAVE SWEAT OR SCREW ENDS, 2-1/2" IN DIAMETER AND OVER SHALL HAVE FLANGED ENDS.

S. DRAIN VALVES SHALL BE PROVIDED WITH HOSE END, BRONZE BODY WITH CAP AND CHAIN.

T. STRAINERS SHALL BE Y-TYPE WITH REMOVABLE SCREEN. TWO-INCH AND SMALLER, SCREWED, MUESSCO #11, 2-1/2" AND LARGER, FLANGED CAST IRON MUESSCO #751 OR APPROVED EQUAL. PROVIDE BRASS SCREENS WITH 1/16" PERFORATIONS FOR WATER UP TO 3" INCLUSIVE AND ALL STEAM SIZES; 1/8" PERFORATIONS FOR 4" AND ABOVE FOR WATER. STRAINERS FOR COLLS REQUIRING AUTOMATIC FLOW LIMITING VALVES SHALL HAVE 20 MESH SCREENS.

ALL WORK SHALL BE PERFORMED BY A LICENSED CONTRACTOR. CONTRACTOR IS TO PROVIDE ALL MATERIALS AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE SYSTEMS INDICATED ON THE DRAWINGS AS SPECIFIED AND AS REQUIRED BY ALL APPLICABLE CODES, ORDINANCES, AND AHJ.

RESTAURANT
RENOVATION


Address: 190 Spruce Ln
Gallatinburg , Tennessee

PROJECT NO.
02222
DATE
09/16/2022
REVISIONS



SHEET NO



M-1.0



GENERIC KITCHEN HOOD DETAIL

GREASE DUCT SHALL MAINTAIN A MINIMUM OF 18" CLEARANCE TO COMBUSTIBLE CONSTRUCTION AND A MINIMUM OF 3" TO NONCOMBUSTIBLE CONSTRUCTION AND GYPSUM WALL BOARD ATTACHED TO A NON-COMBUSTIBLE STRUCTURE OF NO LESS THAN 3". A FIRE WRAP SHALL BE REQUIRED AROUND GREASE EXHAUST DUCT IF DUCT IS LESS THAN 3" FROM A LIMITED COMBUSTIBLE MATERIAL SURFACE

- NOTES:
1. HOOD SHALL BE COMPLETE WITH:
- A) PRE-ENGINEERED, UL LISTED CHEMICAL SUPPRESSION SYSTEM WITH AUTO AND REMOTE ACTIVATION AND CONTROL PANEL.
 - B) UL LISTED PRE-WIRED LIGHT FIXTURES.
 - C) UL CLASSIFIED STAINLESS STEEL BAFFLE TYPE FILTERS.
 - D) SUPPRESSION SYSTEM SHALL COVER ENTIRE AREA UNDER HOOD.
2. HOOD MAKE-UP AIR AND EXHAUST AIR QUANTITIES SHALL BE BALANCED TO QUANTITIES LISTED ON MANUFACTURER'S LABEL AFFIXED TO HOOD.



- DRAWING NOTES:
- 1 KITCHEN EXHAUST HOOD
 - 2 EXPOSED SHEET METAL SPIRAL DUCTWORK WITH LONGITUDINAL SHIMS (TYP.)
 - 3 FIELD FABRICATED SHEET METAL PLENUM BOX
 - 4 CEILING MOUNTED EXHAUST FAN
 - 5 16"Ø SHEET METAL OUTSIDE AIR DUCT UP TO ROOM. OUTSIDE AIR DUCTWORK TO BE CONNECTED TO RETURN PLENUM BOX. PROVIDE A BALANCING DAMPER AND AN AUTOMATIC MOTORIZED DAMPER IN OUTSIDE AIR DUCTWORK
 - 6 PROGRAMMABLE THERMOSTAT
 - 7 SHEET METAL EXHAUST DUCTWORK
 - 8 CONDENSING UNIT ON CONCRETE PAD
 - 9 DUCT MOUNTED SMOKE DETECTOR
 - 10 18x18 SHEET METAL EXHAUST DUCT FROM HOOD UP TO KEF-1
 - 11 PROVIDE VOLUME DAMPER ON 14"Ø ROUND DUCTWORK DROPS INTO DIFFUSERS
 - 12 NEW 15 TON HORIZONTAL AHU. REFER TO M-100 FOR SPECIFICATIONS
 - 13 PROVIDE VOLUME DAMPER ON 10"Ø ROUND DUCTWORK DROPS INTO DIFFUSERS
 - 14 26X16 TO 16X14 TRANSITION SUPPLY DUCT TO KSF-1 FAN OUTLET
 - 15 4"Ø SHEET METAL TOILET EXHAUST DUCT UP TO ROOF.

REFER TO SUPERIOR HOODS PLANS FOR HOOD, EXHAUST FANS AND MAKE UP AIR UNIT SPECS.

NOTES ON SUPERIOR HOODS SYSTEMS

A. GREASE DUCT SPECIFICATIONS:

ALL DUCTWORK SHALL BE DESIGNED, CONSTRUCTED AND INSTALLED IN ACCORDANCE WITH TBCM 2012 SECTIONS 506.3.1 THROUGH 506.3.13.3. ACCESS DOORS/CLEANOUTS AS SHOWN ON PLANS ARE PROPOSED TO COMPLY WITH MINIMUM CODE REQUIREMENTS, THE CONTRACTOR IS RESPONSIBLE FOR FINAL COMPLIANCE AND THE ONES PROVIDED MUST BE RATED AND COMPLY WITH ALL REQUIREMENTS AS PER TBCM 506.3.8.

AS PER TBCM 506.3.7, DUCT SYSTEMS SERVING TYPE I HOOD SHALL BE CONSTRUCTED AND INSTALLED SO THAT GREASE CANNOT COLLECT IN ANY PORTION THEREOF, AND THE SYSTEM SHALL SLOPE NOT LESS THAN ONE-FOURTH UNIT VERTICAL IN 12 UNITS HORIZONTAL (2-PERCENT SLOPE) TOWARD THE HOOD OR TOWARD A GREASE RESERVOIR DESIGNED AND INSTALLED IN ACCORDANCE WITH SECTION 506.3.7.1. DUCT SHOULD BE SLOPED AS MUCH AS POSSIBLE TO REDUCE THE CHANCE OF GREASE ACCUMULATION IN HORIZONTAL RUNS.

IF THE DUCT IS WITHIN 18 INCHES OF COMBUSTIBLE MATERIAL, PROVIDE UL-2221 LISTED DOUBLE WALL GREASE DUCT 20 GAUGE 430 STAINLESS INNER DUCT INSULATED WITH A 24 GAUGE 430 STAINLESS OUTER SHELL.

B. EXHAUST FANS:

- FANS SHALL INCLUDE AMCA SEAL AND SHALL BE U.L. LISTED.
- DISCONNECT SWITCH NEMA 3R - MOUNTED AND WIRED.
- 26" ROOF CURB, FACTORY INCLUDED.
- FAN SPEED CONTROLLER - FACTORY MOUNTED AND WIRED.

AS PER TBCM 506.3.7, DUCT SYSTEMS SERVING TYPE I HOOD SHALL BE CONSTRUCTED AND INSTALLED SO THAT GREASE CANNOT COLLECT IN ANY PORTION THEREOF, AND THE SYSTEM SHALL SLOPE NOT LESS THAN ONE-FOURTH UNIT VERTICAL IN 12 UNITS HORIZONTAL (2-PERCENT SLOPE) TOWARD THE HOOD OR TOWARD A GREASE RESERVOIR DESIGNED AND INSTALLED IN ACCORDANCE WITH SECTION 506.3.7.1.

GREASE DUCT CLEANOUTS SHALL COMPLY WITH ALL THE REQUIREMENTS OF TBCM 506.3.8.

ALL DUCTWORK SHALL BE DESIGNED, CONSTRUCTED AND INSTALLED IN ACCORDANCE WITH TBCM SECTIONS 506.3.1 THROUGH 506.3.13.3.




ALL INFORMATION PERTAINING TO SUPERIOR HOODS SHALL HAVE A SEPERATE PERMIT, DRAWINGS AND PLAN REVIEW.

ALL WORK SHALL BE PERFORMED BY A LICENSED CONTRACTOR. CONTRACTOR IS TO PROVIDE ALL MATERIALS AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE SYSTEMS INDICATED ON THE DRAWINGS AS SPECIFIED AND AS REQUIRED BY ALL APPLICABLE CODES, ORDINANCES, AND AHJ.



ALL WORK SHALL BE PERFORMED BY A LICENSED CONTRACTOR. CONTRACTOR IS TO PROVIDE ALL MATERIALS AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE SYSTEMS INDICATED ON THE DRAWINGS AS SPECIFIED AND AS REQUIRED BY ALL APPLICABLE CODES, ORDINANCES, AND AHJ.

- DRAWING NOTES:
- 1 KITCHEN HOOD EXHAUST FAN (KEF-1)
 - 2 KITCHEN HOOD EXHAUST FAN (KSF-1)
 - 3 15 TON CONDENSING UNIT ON 6" CONCRETE PAD
 - 4 VENT THROUGH ROOM, SHOWN FOR REFERENCE ONLY




HVAC ROOF PLAN

1/4" = 1'-0"




RESTAURANT RENOVATION	PROJECT NO. 02222 DATE 09/16/2022 REVISIONS
Address: 190 Spruce Ln Gatlinburg , Tennessee	 SHEET NO
M-3.0	


ALL WORK SHALL BE PERFORMED BY A LICENSED CONTRACTOR. CONTRACTOR IS TO PROVIDE ALL MATERIALS AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE SYSTEMS INDICATED ON THE DRAWINGS AS SPECIFIED AND AS REQUIRED BY ALL APPLICABLE CODES, ORDINANCES, AND AHJ.




WALL CAP DETAIL
N.T.S.




DUCT BRANCH TAKE OFF DETAIL FOR LOW PRESSURE DUCTWORK
N.T.S.





ROOF CAP DETAIL
N.T.S.



ROOFCAP EXHAUST DETAIL
N.T.S.




CEILING MOUNTED EXHAUST FAN DETAIL
N.T.S.




NOTE: ALL ROOF MOUNTED EQUIPMENT MUST ADHERE TO CURRENT HURRICANE CODES REGARDING ROOF TIE-IN AND WIND RESISTANCE.

ROOF UPBLAST EXHAUST FAN
No Scale



CONDENSATE DRAIN & TRAP DETAIL
N.T.S.



NOTE: ALL ROOF MOUNTED EQUIPMENT MUST ADHERE TO CURRENT HURRICANE CODES REGARDING ROOF TIE-IN AND WIND RESISTANCE.

ROOFTOP SUPPLY FAN
No Scale

RESTAURANT
RENOVATION

Address: 190 Spruce Ln
Gatlinburg, Tennessee

PROJECT NO. 02222
DATE 09/16/2022
REVISIONS

TAYLOR HEIM
REGISTERED ARCHITECT
No. 197680
STATE OF TENNESSEE

SHEET NO

M-5.0

PLUMBING SYMBOL LEGEND

CD	– CONDENSATE DRAIN		CD	– ABOVE GROUND CONDENSATE DRAIN
CO	– CLEANOUT		CD	– BELOW GROUND CONDENSATE DRAIN
CONT	– CONTINUATION			– DOMESTIC COLD WATER
CW	– DOMESTIC COLD WATER			– DOMESTIC HOT WATER
DN	– DOWN			– DOMESTIC HOT WATER RECIRCULATING
EXIST	– EXISTING		S	– SANITARY DRAIN
HW	– DOMESTIC HOT WATER			– SANITARY VENT
IE	– INVERT ELEVATION		ST	– ABOVE GROUND STORM
RPBP	– REDUCED PRESSURE BACKFLOW PREVENTER		ST	– BELOW GROUND STORM
SAN	– SANITARY		STO	– OVERFLOW STORM DRAIN
SF	– SQUARE FEET		STO	– BELOW GROUND OVERFLOW STORM
ST	– STORM			– HOSE BIBB OR WALL HYDRANT
STO	– OVERFLOW STORM DRAIN			– CLEAN OUT PLUG
VTR	– VENT THRU ROOF			– FLOOR CLEAN OUT
IM	– ICE MAKER			– FLOOR DRAIN
SH	– SHOWER			– ROOF DRAIN
BT	– BATHTUB			– FLOOR SINK
LAV	– LAVATORY			– CONNECT TO EXISTING
WC	– WATER CLOSET			– GATE VALVE
S	– SINK			– BALL VALVE
KS	– KITCHEN SINK			– CHECK VALVE(SWING)
IWH	– INSTANTANEOUS WATER HEATER			– REDUCED PRESSURE BACKFLOW PREVENTOR
WMB	– WASH MACHINE BOX			– RELIEF OR SAFETY VALVE
EWB	– ELECTRIC WATER HEATER TANK TYPE			– DIRECTION OF FLOW
				– ELBOW, TURNED DOWN
				– ELBOW, TURNED UP
				– PRESSURE REDUCING VALVE

NOTE: SOME SYMBOLS SHOWN ON THIS LEGEND MAY NOT PERTAIN TO THIS PROJECT.

PLUMBING SPECIFICATIONS

- 1.00 – GENERAL PROVISIONS
- 1.1 PROVIDE ALL LABOR, MATERIAL AND EQUIPMENT FOR A COMPLETE AND PROPERLY OPERATING PLUMBING SYSTEM.
- 1.2 CODES AND STANDARDS: ALL PLUMBING WORK SHALL BE IN STRICT COMPLIANCE WITH THE STANDARD PLUMBING CODE AND ALL LOCAL CODES HAVING JURISDICTION.
- 1.3 ALL PLUMBING WORK SHALL BE DONE IN A NEAT AND WORKMANLIKE MANNER.
- 1.4 CONTRACTOR SHALL SECURE AND PAY FOR ALL PERMITS AND FEES, ETC., REQUIRED FOR THE EXECUTION OF THIS WORK.
- 1.5 CONTRACTOR SHALL COORDINATE HIS WORK WITH ALL OTHER TRADES BEFORE FABRICATION OR INSTALLATION. OFFSETS AND/OR TRANSITIONS REQUIRED SHALL BE PROVIDED WITHOUT ADDITIONAL COST. CONTRACTOR SHALL COORDINATE AND INSTALL HIS WORK IN A TIMELY MANNER TO PREVENT DELAYS IN THE CONSTRUCTION.
- 1.6 CONTRACTOR SHALL BE RESPONSIBLE TO REPAIR OR REPLACE DAMAGED EQUIPMENT AND/OR MATERIAL.
- 1.7 PROVIDE ALL MATERIALS REQUIRED TO PROPERLY SUPPORT ALL PIPING AND EQUIPMENT. PIPE HANGERS SHALL BE ADJUSTABLE TYPE AND BE SPACED IN ACCORDANCE WITH THE STANDARD PLUMBING CODE. PROVIDED PLASTIC COATED RING ON HANGERS FOR COPPER PIPING TO PROVIDE DIELECTRIC ISOLATION.
- 1.8 PROVIDE DIELECTRIC UNIONS OR FLANGES BETWEEN COPPER AND STEEL PIPING AND BETWEEN BRASSWARE AND STEEL. DO NOT USE STEEL AND COPPER PIPING IN THE SAME SYSTEM WITHOUT SUCH ISOLATION.
- 1.9 PROVIDE REDUCING FITTINGS (REDUCING BUSHINGS SHALL NOT BE USED) WHERE CHANGES IN PIPE SIZES OCCUR.
- 1.10 THIS CONTRACTOR SHALL SUPPLY AND INSTALL ALL SERVICES THROUGHOUT THE BUILDING AND MAKE CONNECTION TO SITE UTILITIES APPROXIMATELY 5'-0" OUTSIDE THE BUILDING. CONTRACTOR SHALL SUPPLY AND INSTALL FIXTURES, FITTINGS, VALVING AND TRIM AND MAKE READY FOR USE ALL FIXTURES, EQUIPMENT, ETC.
- 1.11 SEE ARCHITECTURAL DRAWINGS FOR FIXTURE LOCATIONS AND MOUNTING HEIGHTS.
- 2.00 – BASIC MATERIALS AND METHODS
- 2.1 ABOVEGROUND WATER PIPE AND FITTINGS – TYPE "L" COPPER.
- 2.2 PROVIDE UNIONS OR FLANGES IN ALL DOMESTIC WATER SERVICE LINES AT EACH PIECE OF EQUIPMENT, SPECIALTY VALVES OR AT OTHER LOCATIONS REQUIRED FOR READY DISCONNECT.
- 2.3 WATER HAMMER ARRESTORS SHALL BE INSTALLED AT THE LOCATIONS ON THE PLANS AND IN ACCORDANCE WITH PDI STANDARD WH-201. PRODUCTS SHALL BE EQUAL TO THOSE MANUFACTURED BY PRECISION PLUMBING PRODUCTS OR SIOUX CHIEF.
- 2.4 VALVES: PROVIDE VALVES TO ISOLATE EACH RISER, BRANCH LINE AND PIECE OF EQUIPMENT.
- 2.5 PROVIDE PRESSURE REDUCING VALVE AND AIR GAP CONNECTION AT DISHWASHER AS REQUIRED BY CODE AND ACCORDING TO MANUFACTURER.
- 2.6 PROVIDE INLINE WATER FILTER AT COFFEE MAKER AND ICE MAKER TO REMOVE MATERIALS, TASTE AND ODOR – "EVERPURE OR "SYSTEMS IV".
- 2.7 ABOVEGROUND SANITARY, WASTE, SANITARY VENT AND STORM PIPING – PVC (DWV) SOLID WALL SHALL BE PERMITTED TO BE USED. PVC (DWV) SHALL NOT BE USED IN RETURN AIR PLENUMS.
- 2.8 BELOWGROUND SANITARY, WASTE AND VENT – PVC (DWV) SOLID WALL SHALL BE PERMITTED TO BE USED. PVC SHALL NOT BE USED FOR DRAINAGE IN HIGH TEMPERATURE DISCHARGE AREAS SUCH AS KITCHENS AND BOILER ROOMS.
- 2.9 INSTALL GRAVITY LINES SLOPED AT 1/8" PER FOOT FOR PIPE 3" AND LARGER AND 1/4" PER FOOT FOR PIPE SMALLER THAN 3". VERIFY INVERT ELEVATION WITH SITE PIPING PRIOR TO ANY PIPE BEING INSTALLED.
- 3.00 – PLUMBING FIXTURES AND TRIM
- 3.1 ALL PLUMBING FIXTURES SHALL BE "FIRST QUALITY" AS DEFINED AND SET FORTH IN COMMERCIAL STANDARD C577-28 AS PROMULGATED BY THE U.S. DEPARTMENT OF COMMERCE.
- 3.2 ALL FIXTURES ARE TO BE WHITE VITREOUS CHINA UNLESS OTHERWISE SPECIFICALLY NOTED.
- 3.3 FIXTURES AND FITTINGS PROPOSED SHALL BE FROM ONE MANUFACTURER AND OF SIMILAR CHARACTER IN ANY ROOM OR LOCATION. ESCUTCHEONS, HANDLES, ETC., ON THE DIFFERENT FIXTURES SHALL BE OF THE SAME DESIGN.
- 3.4 PROVIDE FIXTURE CARRIERS AS RECOMMENDED BY FIXTURE MANUFACTURER AND/OR CONSTRUCTION METHOD.
- 3.5 PROVIDE ACCESS PANELS TO ALL VALVES WITHIN CHASES OR ABOVE NON-ACCESSIBLE CEILINGS. REFER TO ARCHITECTURAL DRAWINGS FOR CEILING TYPES.
- 3.6 FLOOR DRAIN TRAP SEALS SHALL HAVE AN APPROVED AUTOMATIC PRIMING DEVICE DESIGNED FOR THAT PURPOSE.
- 3.7 ALL CONCEALED TRAPS, PRIMERS, VALVES, CLEANOUTS, ETC. LOCATED IN TILED AREAS SHALL BE PROVIDED WITH AN ACCESS PANEL.
- 4.00 – INSULATION
- 4.1 ABOVE GROUND HOT WATER – FIBERGLASS, 1" THICKNESS, ASJ JACKET, DOUBLE SEALING LAP JOINT, 0.24 K AT 75°. INSULATION AND ADHESIVES INSTALLED IN RETURN AIR PLENUMS SHALL HAVE A MAXIMUM FLAME SPREAD RATING OF 25 AND A MAXIMUM SMOKE DEVELOPED RATING OF 50.
- 4.2 ABOVEGROUND CONDENSATE PIPING SHALL BE 1/2" FLEXIBLE UNICELLULAR POLYOLEFIN FOAM AND SHALL HAVE A MAXIMUM FLAME SPREAD RATING OF 25 AND A MAXIMUM SMOKE DEVELOPED RATING OF 50 – IMCOA "IMCOLOCK"
- 5.00 – VALVES AND COCKS
- 5.1 VALVES 2" AND SMALLER SHALL BE BALL VALVES, 150 PSI SWP, 400 PSI WOG. STANDARD PORT BALL, BRONZE TRIM, CAST BRONZE BODY, CHROMIUM-PLATED BRASS BALL, BRONZE NON-BLOWOUT STEM, TEFLON SEAT, DOUBLE O-RING STEM SEALS, ZINC-COATED STEEL HANDLE WITH PLASTIC COATED HAND GRIP, 90 DEGREE OPERATION FROM FULL OPEN TO TIGHT SHUT-OFF – STOCKHAM S214-BR-T-I, STOCKHAM S216-BR-T-S OR EQUAL.
- 5.2 CHECK VALVES, ROUGH BRASS, REGRINDING BRONZE DISC – STOCKHAM B-345; B-309 OR EQUAL.
- 6.00 – STERILIZATION
- 6.1 DOMESTIC WATER PIPING SHALL BE THOROUGHLY FLUSHED OUT AND STERILIZED IN ACCORDANCE WITH THE STANDARD PLUMBING CODE.

PLUMBING GENERAL NOTES

1. READ THE SPECIFICATIONS.
2. UTILITIES AND SERVICES INDICATED ARE TAKEN FROM VARIOUS OLD AND NEW SURVEYS, AS-BUILT RECORDS AND FIELD INVESTIGATIONS. UNFORSEEN CONDITIONS PROBABLY EXIST AND NEW WORK MAY NOT BE FIELD LOCATED EXACTLY AS SHOWN ON DRAWINGS. COOPERATION WITH OTHER TRADES IN ROUTING AND BURIAL DEPTHS, AS DETERMINED DURING CONSTRUCTION WILL BE NECESSARY.
3. FIELD VERIFY EXISTING INSTALLATIONS. MODIFY EXISTING PLUMBING SYSTEMS, WHICH ARE TO REMAIN ACTIVE, TO FACILITATE RECONNECTION AND EXTENSION OF THE NEW WORK.
4. NOTIFY OWNER AT LEAST 24 HOURS PRIOR TO INTERRUPTING EXISTING SERVICE. SCHEDULE DISCONNECTION AND TIE-INS TO MINIMIZE DISRUPTION OF SERVICES. SERVICES ARE NOT TO BE LEFT DISRUPTED DURING NON-NORMAL CONTRACTOR WORKING HOURS.
5. PIPE ROUTING SHOWN IS SCHEMATIC AND IS NOT INTENDED TO INDICATE EXACT ROUTING AND ANY ADDITIONAL OFFSETS AND FITTINGS REQUIRED FOR PROPER INSTALLATION AND TO MAINTAIN CLEARANCES. VERIFY STRUCTURAL, MECHANICAL AND ELECTRICAL INSTALLATIONS AND OTHER POTENTIAL OBSTRUCTIONS AND ROUTE PIPING TO AVOID INTERFERENCES.
6. PROVIDE ALL OFFSETS AND FITTINGS AND MAKE CONNECTION TO SITE UTILITIES.
7. CONCEAL PIPING ABOVE CEILINGS, WITHIN WALLS OR CHASES EXCEPT IN MECHANICAL ROOMS OR AS SPECIFICALLY NOTED. PROVIDE ACCESS PANELS FOR ALL VALVES CONCEALED IN WALLS OR ABOVE NON-ACCESSABLE CEILINGS.
8. SLEEVE AND FIRE STOP PENETRATIONS OF RATED WALLS, FLOORS, CEILINGS AND ROOFS. FLASH AND COUNTERFLASH ROOF PENETRATIONS.
9. WHEN BEAM SLEEVE PENETRATIONS ARE NECESSARY, COORDINATE PENETRATIONS WITH ALL TRADES, THE ARCHITECT AND THE STRUCTURAL ENGINEER.
10. PROVIDE FOUNDATION PAD PENETRATION SLEEVES. ALLOW 1" MINIMUM CLEARANCE BETWEEN SLEEVE INSIDE SURFACE AND PIPE EXTERIOR.
11. SEE ARCHITECTURAL DRAWINGS FOR FIXTURE LOCATIONS AND MOUNTING HEIGHTS.
12. PROVIDE AUTOMATIC TRAP PRIMERS FOR FLOOR DRAIN TRAP SEALS.
13. PROVIDE, WHEN REQUIRED BY CODE, AN AIR GAP SERVING INDIVIDUAL FIXTURES, DEVICES, APPLIANCES AND APPARATUS.
14. ALL EXPOSED PIPE AND FITTINGS IN FINISHED AREAS SHALL BE CHROME PLATED.
15. MOUNT HOSE BIBBS 24" ABOVE FINISH GRADE.
16. PROVIDE CLEANOUTS IN ACCORDANCE WITH APPROPRIATE CODES AND REGULATIONS.
17. COORDINATE EXACT FLOOR DRAIN LOCATIONS WITH ARCHITECTURAL DRAWINGS. SET FLOOR DRAINS BELOW FINISH FLOOR TO ALLOW FOR FLOOR SLOPING TO THE DRAIN.
18. PROVIDE ALL OFFSETS AND FITTINGS AND MAKE CONNECTION TO SITE UTILITIES.
19. COORDINATE PIPING WITH ALL ELECTRICAL EQUIPMENT(PANELS, TRANSFORMERS, ETC.) PRIOR TO ANY INSTALLATION. DO NOT ROUTE ANY PIPING OVER ANY ELECTRICAL PANELS UNDER ANY CIRCUMSTANCES. ANY PIPING RUN OVER PANELS SHALL BE REROUTED AT NO ADDITIONAL COST.
20. PVC (DWV) PIPE SHALL NOT BE PERMITTED IN AREAS OF HIGH WASTE TEMPERATURE. WATER, SUCH AS KITCHENS AND BOILER ROOMS.

ALL WORK SHALL BE PERFORMED BY A LICENSED CONTRACTOR. CONTRACTOR IS TO PROVIDE ALL MATERIALS AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE SYSTEMS INDICATED ON THE DRAWINGS AS SPECIFIED AND AS REQUIRED BY ALL APPLICABLE CODES, ORDINANCES, AND AHJ.

TABLE 308.5 HANGER SPACING		
PIPING MATERIAL	MAXIMUM HORIZONTAL SPACING (feet)	MAXIMUM VERTICAL SPACING (feet)
ABS pipe	4	10b
Aluminum tubing	10	15
Brass pipe	10	10
Cast-iron pipe	5a	15
Copper or copper-alloy pipe	12	10
Copper or copper-alloy tubing, 1 1/4-inch diameter and smaller	6	10
Copper or copper-alloy tubing, 1 1/2-inch diameter and larger	10	10
Cross-linked polyethylene (PEX) pipe	2.67 (32 inches)	10b
Cross-linked polyethylene/ aluminum/cross-linked polyethylene (PEX-AL-PEX) pipe	2.67 (32 inches)	4
CPVC pipe or tubing, 1 inch and smaller	3	10b
CPVC pipe or tubing, 1 1/4 inches and larger	4	10b
Steel pipe	12	15
Lead pipe	Continuous	4
Polyethylene/aluminum/ polyethylene (PE-AL-PE) pipe	2.67 (32 inches)	4
Polyethylene of raised temperature (PE-RT) pipe	2.67 (32 inches)	10b
Polypropylene (PP) pipe or tubing 1 inch and smaller	2.67 (32 inches)	10b
Polypropylene (PP) pipe or tubing, 1 1/4 inches and larger	4	10b
PVC pipe	4	10b
Stainless steel drainage systems	10	10b
For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm.		
a. The maximum horizontal spacing of cast-iron pipe hangers shall be increased to 10 feet where 10-foot lengths of pipe are installed.		
b. Mdstory guide for sizes 2 inches and smaller.		

GAS WATER HEATER TANKLESS WITH CIRCULATION PUMP SCHEDULE (EACH)

MARK	QUANTITY	LOCATION	GAS CONNECTION	GAS CONSUMPTION	GPM AT 45°F TEMP RISE	ENERGY FACTOR	MANUFACTURER/ MODEL NUMBER	PUMP VOLTAGE/HP	DIMENSIONS HxWxD (INCH)
GWH-1	2	EXTERIOR	3/4"	199.000 BTU/H	8.5	0.95	WESTINGHOUSE WGRGH 199 O	120V-1PH-60Hz 100W	36.8" x 17.6" x 16.7", 120 LBS WEIGHT

PLUMBING SPECIFIC NOTES:

- 1.BATHROOM WALL AND FLOOR SHALL HAVE A SMOOTH, HARD, NON-ADSORBENT SURFACE PER SECTION 1210.1 OF IPC 2012
- 2.ALL STEEL STUDS SUPPORTING ALL WALL HUNG PLUMBING FIXTURES SHALL BE DOUBLE OR NO LESS THAN 20 GAUGE PER SECTION 2517.5.1.1 OF IPC 2012
- 3.PROVIDE WATER HAMMER ARRESTORS IN ALL QUICK CLOSING VALVES.
- 4.PROVIDE FIXTURE COMPLIANCE WITH REFERENCE STANDARDS PER FBC PLUMBING SECTION 406 TO 421
- 5.ALL PLUMBING FIXTURES SHALL COMPLY WITH MIAMI DADE COUNTY ORDINANCE #08-14 FOR PLUMBING FIXTURES MAXIMUM FLOW RATE AND CONSUMPTION.
- 6.DOMESTIC WATER SHALL USE COPPER PIPE TYPE L. SANITARY AND WASTE SHALL USE SOLID DWV PVC.

SLOPE OF HORIZONTAL DRAINAGE PIPE:

PIPE SIZES OF 2½" OR LESS SHALL BE RUN AT A SLOPE OF 1/4" PER FOOT
PIPE SIZES OF 3" TO 6" SHALL BE RUN AT A SLOPE OF 1/8" PER FOOT
PIPE SIZES OF 8 OR LARGER SHALL BE RUN AT A SLOPE OF 1/16" PER FOOT

PLUMBING FIXTURES CLEARANCES

–A WATER CLOSET, URINAL, LAVATORY OR BIDET SHALL NOT BE SET CLOSER THAN 15" FROM ITS CENTER TO ANY SIDE WALL, PARTITION, VANITY OR OTHER OBSTRUCTION, OR CLOSER THAN 30" CENTER TO CENTER BETWEEN ADJACENT FIXTURES. THERE SHALL BE AT LEAST A 21" CLEARANCE IN FRONT OF THE WATER CLOSET, URINAL, LAVATORY OR BIDET TO ANY WALL, FIXTURE OR DOOR. WATER CLOSET COMPARTMENTS SHALL NOT BE LESS THAN 30" WIDE AND 60: DEEP.

NOTE:

1.–VISIT AND CAREFULLY EXAMINE THOSE PORTIONS OF THIS BUILDING AND SITE AFFECTED BY THIS WORK BEFORE SUBMITTING PROPOSALS, SO AS TO BECOME FAMILIAR WITH THE EXISTING CONDITIONS AND DIFFICULTIES THAT WILL AFFECT EXECUTION OF THE WORK. SUBMISSION OF A PROPOSAL WILL BE CONSTRUE AS EVIDENCE THAT SUCH EXAMINATION HAS BEEN MADE AND LATER CLAIMS FOR LABOR, EQUIPMENT OR MATERIALS REQUIRED BECAUSE OF DIFFICULTIES WILL NOT BE RECOGNIZED. PLANS SHOW A GENERAL DESCRIPTION OF THE ENGINEER INTENTION AS TO THE SCOPE OF WORK, CONTRACTOR SHALL VISIT THE JOB SITE TO FAMILIARIZE WITH THE PLACE AND BRING TO THE ARCHITECT/ENGINEER ANY DISCREPANCIES WITH CONSTRUCTION DOCUMENTS. CONTRACTOR SHALL PROVIDE THE ENGINEER WITH SUBMITTALS OF ALL EQUIPMENT AND MATERIALS INTENDED TO USE TO COMPLETE THE WORK.

PLUMBING FIXTURE CONNECTION SCHEDULE

NO.	DESCRIPTION	WASTE	VENT	WATER		REMARKS
				COLD	HOT	
WC	WATER CLOSET	3"	2"	1/2"	--	TYPE TANK, 1.28 GPF, FLOOR MOUNTED.
LAV	LAVATORY	1 1/4"	2"	1/2"	1/2"	AS SELECTED BY OWNER. PROVIDE 0.5 GPM FAUCET [1]
HS	KITCHEN HAND SINK	1-1/2"	2"	1/2"	1/2"	AS SELECTED BY OWNER. PROVIDE 1.0 GPM FAUCET [1]

[1] PROVIDE ANTI-SCALD VALVE THERMOSTATIC MIXING VALVE

NOTES:
1.– All exposed trim, such as P-traps, angle stops, and supplies shall be chrome plated.
2.– All fixtures shall comply with Reference Standards as per IPC 2012 Plumbing 406 through 421.
3.– All Plumbing Fixtures to be specified by Architect. Please see Architectural Drawing for further information.

PLUMBING DRAWING INDEX

SHEET	DESCRIPTION	ISSUED
P-0.0	PLUMBING LEGEND, NOTES & SCHEDULES	YES
P-1.0	PLUMBING SITE PLAN	YES
P-2.0	PLUMBING FLOOR PLAN	YES
P-3.0	PLUMBING DETAILS	YES

RESTAURANT
RENOVATION

Address: 190 Spruce Ln
Gatlinburg , Tennessee

PROJECT NO.
02222
DATE
09/16/2022
REVISIONS




SHEET NO

P-0.0

PLUMBING SITE PLAN


1/8" = 1'-0"



RESTAURANT
RENOVATION

Address: 190 Spruce Ln
Gallatinburg , Tennessee

PROJECT NO.
02222
DATE
09/16/2022
REVISIONS




SHEET NO


P-1.0

ALL WORK SHALL BE PERFORMED BY A LICENSED CONTRACTOR. CONTRACTOR IS TO PROVIDE ALL MATERIALS AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE SYSTEMS INDICATED ON THE DRAWINGS AS SPECIFIED AND AS REQUIRED BY ALL APPLICABLE CODES, ORDINANCES, AND AHJ.

ALL WORK SHALL BE PERFORMED BY A LICENSED CONTRACTOR. CONTRACTOR IS TO PROVIDE ALL MATERIALS AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE SYSTEMS INDICATED ON THE DRAWINGS AS SPECIFIED AND AS REQUIRED BY ALL APPLICABLE CODES, ORDINANCES, AND AHJ.




OUTDOOR GAS WATER HEATER TANKLESS WITH BUILT IN PUMP DETAIL (TWO UNITS)
N.T.S.



DRY WELL
No Scale


1



THE HANDLE OF THE FLUSH LEVER SHALL FACE THE WIDE SIDE OF THE STALL (NO EXCEPTIONS).


WATER CLOSET
No Scale

2



INSULATED PIPE HANGER
No Scale

3



- NOTE:
1. REFER TO SPECIFICATIONS AND FLOOR PLANS FOR MATERIAL AND SIZES
 2. SPECIFIED HANGER ROD, STRUT, NUTS, WASHER, AND PIPE STRAPS SHALL BE OF GALVANIZED PLATED MATERIALS


TRAPEZE HANGER
No Scale

4

RESTAURANT
RENOVATION

Address: 190 Spruce Ln
Gallatinburg , Tennessee

PROJECT NO.
02222
DATE
09/16/2022
REVISIONS




SHEET NO

P-3.0

SPECIFICATION AND SUBMITTAL

GB-500-B 100 GPM 99% Efficient Grease Interceptor for Indoor/Outdoor Installation



This unit is certified to ASME A112.14.3 (Type D) and CSA B481.1. This unit does not require flow control.

Satisfies Miami DERM 99% efficiency requirements. Product labels are permanently attached to inside and outside of unit for easy viewing.

SUBMITTAL

Standard

Location: indoor/outdoor
Installation: above/below grade
Flow Rate / Certified Grease Capacity: 100 GPM (6.3 US / 2,348 lbs.)
Removal Efficiency at the Rated Capacity: 98.9%
99% Efficiency Rating: 2,817 lbs. certified grease capacity @ 99.2% efficiency
Solids Capacity: 102 gal.
Liquid Capacity: 510 gal.
Weight: 568 lbs.
Connections: 4" (100 mm) FPT / plain end triple-inlet/triple-outlet
Cover: gas/water tight pickable cast iron with H20 lb. load rating

Options

☐ 6" plain end inlet/outlet (straight-through)
☐ 6" plain end inlet/outlet (straight-through) with dual pumpout port connections
☐ 6" plain end inlet/outlet (triple outlet)
☐ 6" MPT inlet/outlet (stainless steel, straight-through)
☐ -FO (fixed outlet)
☐ C24HZ: Highway rated bolted composite covers - 16,000 lbs.
☐ CC2: Integral membrane clamping collar kit

☐ AGS2: Above Grade Support
☐ AK2: High Water Anchor Kit
☐ PP3: Pumpout Port
Field Cut Risers
☐ FCR2 (x2) >4" - 34"
☐ FCR2 (x4) >34" - 64"
☐ FCR2 (x6) >64" - 94"

Approval

Signature: _____ Date: _____ Company: _____

Specifying Engineer: _____ Engineering Firm: _____

SCHIER LIFETIME GUARANTEED GREASE INTERCEPTORS

MODEL NUMBER: GB-500-B

DESCRIPTION: 100 GPM Polyethylene Grease Interceptor

PART #: 4075-005-01 DWG BY: B. Karrer DATE: 7/9/2019 REV: _____ ECO: _____

9500 Woodend Road | Edwarsville, KS 66111 | Tel: 913-951-3300 | www.schierproducts.com

© Copyright 2019 Schier, All Rights Reserved

page 1 of 3



TEST REPORT

15001 East Philadelphia Street
Ontario, California - USA 91761-2816
Ph: 909.472.4100 | Fax: 909.472.4243
http://www.iapmoil.org

Report Number: 1757-19023 Project Number: 31448

Report Issued: May 20th, 2019

Client: Schier Products
9500 Woodend Rd.
Edwardsville, KS 66111

Contact: Charlie Ismert

Source of Samples: Samples were manufactured at the client's facility in Edwardsville, KS. The sample was witnessed tested by Dale E. Holloway of IAPMO R&T Lab. Samples are manufactured in good condition.

Date of Testing: May 13th, 2019 through May 17th, 2019

Sample Description: HDPE Grease Interceptor.

Model: GB-500-B (100 gpm)

Refer to the manufacturer's drawings and installation instructions for more detailed measurements and information.

Scope of Testing: The above grease interceptor was witnessed tested to meet the requirements of ASME A112.14.3-2018 "Hydromechanical Grease Interceptors", and CSA B481.0 and B481.1-12 "Grease Interceptors".

Conclusion: The GB-500-B (100 gpm) Grease Interceptor DID COMPLY with the requirements of ASME A112.14.3-2018 "Hydromechanical Grease Interceptors" and CSA B481.0 and B481.1-12 "Grease Interceptors".

By the signature below, I certify that all the testing and preparation for this report was performed under direct supervision of IAPMO R&T Lab, unless otherwise stated.

Witness tested and reported by,

Dale E. Holloway


Dale E. Holloway, Regional Technical Manager
IAPMO R&T Lab

All testing and sample preparation for this report was performed under the continuous, direct supervision of IAPMO R&T Lab, unless otherwise stated. The observations, test results and conclusions in this report apply only to the specific samples tested and are not indicative of the quality or performance of similar or identical products. Only the Client shown above is authorized to copy or distribute the report, and then only in its entirety. Any use of the IAPMO R&T Lab name for the sale or advertisement of the tested material, product or service must first be approved in writing by IAPMO R&T Lab.

"GB-500-B" (100 gpm) Grease Interceptor					INCREMENTAL				ACCUMULATED			
Test No.	Grease Sink	Water Sink	Drop Time (sec)	Flow Rate (GPM)	Lbs added	Lbs skimmed	Lbs retained	Efficiency (%)	Lbs added	Lbs skimmed	Lbs retained	Efficiency (%)
142	2	1	111	102.7	20	0.52	19.48	97.4	2840	22.22	2817.78	99.2
143	1	2	109	104.6	20	0.64	19.36	96.8	2860	22.86	2837.14	99.2
144	2	1	109	104.6	20	0.58	19.42	97.1	2880	23.44	2856.56	99.2
145	1	2	109	104.6	20	0.86	19.14	95.7	2900	24.30	2875.70	99.2
146	2	1	109	104.6	20	1.43	18.57	92.9	2920	24.73	2894.27	99.1
147	1	2	111	103.6	20	1.54	18.46	92.3	2940	27.27	2912.73	99.1
148	2	1	110	102.7	20	1.74	18.26	91.3	2960	29.01	2930.99	99.0
149	1	2	111	102.7	20	2.91	17.09	85.5	2980	31.92	2948.08	98.9
150	2	1	109	104.6	20	4.62	15.38	76.9	3000	36.54	2963.46	98.7
151	1	2	109	104.6	20	5.46	14.54	72.7	3020	42.00	2978.00	98.6
99% efficiency												
Performance Rating												

Report No. 1757-19023

Page 14 of 14



SPECIFICATION SHEET

ASSEMBLY NUMBER: 900-0194-01

DESCRIPTION: DETAIL OF GB-500-B WITH 72" EXTENSION TO SHOW PUMPER HAS ACCESS TO ENTIRE TANK

PROPRIETARY AND CONFIDENTIAL. THE INFORMATION CONTAINED HEREIN IS THE PROPERTY OF SCHIER PRODUCTS. IT IS TO BE USED ONLY FOR THE PURPOSES SPECIFIED HEREIN. NO PART OF THIS DOCUMENT IS TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT PERMISSION IN WRITING FROM SCHIER PRODUCTS.

SHEET: 1 OF 1

DWG BY: TEU DATE: 11/14/19 REV: - ECO: -


Todd Uhlenhake

SCHIER PRODUCTS
9500 Woodend Road
Edwardsville, KS 66111
Tel: 800-827-7119
Fax: 800-827-7664
www.schierproducts.com

ALL WORK SHALL BE PERFORMED BY A LICENSED CONTRACTOR. CONTRACTOR IS TO PROVIDE ALL MATERIALS AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE SYSTEMS INDICATED ON THE DRAWINGS AS SPECIFIED AND AS REQUIRED BY ALL APPLICABLE CODES, ORDINANCES, AND AHJ.

SPECIFICATION AND SUBMITTAL

SI-75 125 Gallon Billy Goat™ Indoor/Outdoor Kitchen Solids Interceptor



SUBMITTAL

Standard

Location: indoor/outdoor
Installation: above/below grade
Solids Capacity: 125 gal. (48 US)
Flow Rate (F): 125 GPM (2.3 US)
Flow Rate (F): 375 GPM (2.3 US)
Liquid Capacity: 125 gal. (48 US)
Weight: 100 lbs. (90 kg)
Connections: 4" FPT with 4" plain end adapters, single inlet and triple outlet.
Cover: Cast iron cover, pickable 34" gas/water tight, H=20 rated, proof-load tested to 40,000 lbs.
Accessories: Schier Safety Star™ (48 lb. rating) built into cover adapter

Options

☐ 6" plain end inlet/outlet (straight-through) with dual pumpout port connections
☐ CMAS: Composite covers, bolted 24" gas/water tight, traffic load rated for 16,000 lbs.
☐ AK2: High water anchor kit
☐ CC2: Integral membrane clamping collar kit
☐ PP3: Pumpout port
PLAIN-EA-24: 2" plain and fitting
PLAIN-EA-34: 4" plain and fitting
FPT-EA-34: 4" x 5" FPT fitting
FPT-EA-28: 2" x 2" FPT fitting

Accessories

☐ FCR2: 14" - 34" field cut riser
☐ FCR2 (x2): 14" - 34" field cut risers
☐ FCR2 (x3): 14" - 34" field cut risers
☐ CA2: Adapter for 24" corrugated clear riser
☐ AK2: High water anchor kit
☐ CC2: Integral membrane clamping collar kit
☐ PP3: Pumpout port
PLAIN-EA-24: 2" plain and fitting
PLAIN-EA-34: 4" plain and fitting
FPT-EA-34: 4" x 5" FPT fitting
FPT-EA-28: 2" x 2" FPT fitting

Approval

Signature: _____ Date: _____ Company: _____

Specifying Engineer: _____ Engineering Firm: _____

SCHIER

MODEL NUMBER: SI-75

DESCRIPTION: 125 Gallon Polyethylene Kitchen Solids Interceptor

PART #: 5045-002-01 DWG BY: B. Karrer DATE: 6/23/2020 REV: _____ ECO: _____

9500 Woodend Road | Edwarsville, KS 66111 | 913-951-3300 | schierproducts.com

© Copyright 2020 Schier, All Rights Reserved

page 1 of 4

SPECIFICATIONS

NOTES

- 4" plain end inlet/outlet (field modifiable to 6" plain end) Unit weight: 9 lbs.
- Maximum operating temperature: 150° F continuous
- Offset connections
- 2 rolls of 35" x 2" butyl mastic tape provided for sealing build-your-own riser joints.


ENGINEER SPECIFICATION GUIDE

Schier Sewer Viewer™ sampling port model # SV10 shall be lifetime guaranteed and made in USA of seamless, rotationally-molded polyethylene. Sampling port shall be furnished for above or below grade installation. Cover shall provide water/ gas-tight seal and have maximum 16,000 lbs. load capacity.


ENGINEER SPECIFICATION GUIDE

Schier Sewer Viewer™ sampling port model # SV10 shall be lifetime guaranteed and made in USA of seamless, rotationally-molded polyethylene. Sampling port shall be furnished for above or below grade installation. Cover shall provide water/ gas-tight seal and have maximum 16,000 lbs. load capacity.

INLET END VIEW



SIDE VIEW



SCHIER

MODEL NUMBER: SV10

DESCRIPTION: Polyethylene Wastewater Sampling Port

PART #: 8069-001-01 DWG BY: B. Karrer DATE: 3/7/2020 REV: _____ ECO: _____

9500 Woodend Road | Edwarsville, KS 66111 | 913-951-3300 | schierproducts.com

© Copyright 2020 Schier, All Rights Reserved

page 3 of 3

SPECIAL PRECAUTIONS
For Schier Grease Interceptor Installations - Failure to follow this guidance voids your warranty

WARNING! DO NOT AIR TEST UNIT OR RISER SYSTEM! Doing so may result in property damage, personal injury or death.

CAUTION! Do not install this unit in any manner except as described in these instructions.

Hydrostatic Slabs (or Pressure Slabs)
When installed under a hydrostatic slab (slab designed to withstand upward lift, usually caused by hydrostatic pressure) interceptor must be enclosed in a watertight concrete vault.

High Water Table Installations
Interceptors and risers are not designed to withstand water table height in excess of the top of the unit when buried (see figure). If it is possible for this to occur, install the interceptor and risers in a water-tight concrete vault or backfill with concrete or flowable fill (wet concrete and flowable backfill should be poured in stages to avoid crushing the interceptor). At risk areas include but are not limited to tidal surge areas, floodplains and areas that receive storm water. Great Basin™ models that are direct buried in high water table scenarios must be installed with an anchor kit. Models GB-50, GB-75, and GB-250 use model AK2 anchor kit. Model GB-500 uses model AK2 anchor kit for use with deadman anchors.

Above Grade Installation Support (for Model GB-500 Only)
The wet weight of the interceptor combined with high temperature kitchen water creates the potential for tank deformation when installed above grade. Model GB-500 installed above grade must be installed with Above Grade Support Kit model AGS2 to maintain structural integrity.

High Temperature Kitchen Water
If water is entering the interceptor at excessive temperature (over 150° F), a drain water tempering valve (DWT) and approved backflow prevention assembly must be installed. Most state and local plumbing codes prohibit water above 150° F being discharged into the sanitary sewer. Water above 150° F will weaken or deform PVC Schedule 40 pipe, poly drainage fixtures like interceptors and erode the coating of cast iron (leading to eventual failure).

DO NOT COMPACT BACKFILL

RESTAURANT RENOVATION

Address: 190 Spruce Ln
Gatlinburg, Tennessee

PROJECT NO. 02222
DATE 09/16/2022
REVISIONS



SHEET NO

P-4.0